

USE TYPEWRITER OR BALL
POINT PEN-PRESS FIRMLY,
PRINT CLEARLY.

Bell Farms #6

WATER WELL RECORD
KSA 82a-1201-1215

Kansas Department of Health and
Environment-Division of Environment
(Water well Contractors)
Topeka, Kansas 66620

1. Location of well:		County Ford	Fraction SE 1/4 SE 1/4 SW 1/4	Section number 20	Township number T 27 S	Range number R 24 E/W
2. Distance and direction from nearest town or city: 4 mi south and 2 1/2 east Dodge City Street address of well location if in city:			3. Owner of well: Ralph Monger R.R. or street: 2007 East Lane City, state, zip code: Dodge City, Kansas			
4. Locate with "X" in section below: N W E S 1 Mile 1 Mile		Sketch map: 		6. Bore hole dia. 28 in. Completion date 7-2-76 Well depth 180 ft.		
5. Type and color of material		From	To	7. Cable tool Rotary Driven Dug Hollow rod Jetted Bored <input checked="" type="checkbox"/> Reverse rotary		
Surface		0	3	8. Use: Domestic Public supply Industry <input checked="" type="checkbox"/> Irrigation Air conditioning Stock Lawn Oil field water Other		
Sandy brown clay		3	30	9. Casing: Material Metal Height: Above or below Threaded Welded <input checked="" type="checkbox"/> Surface 10 in. RMP PVC Weight 31.66 lbs./ft. Dia. 16 in. to 180 ft. depth Wall Thickness: inches or Dia. in. to ft. depth gage No. 188		
Med. sand with 15% clay mixed		30	46	10. Screen: Manufacturer's name W.A. Brown Free-flow Type 10% Dia. 16 Slot/gauze 1/8 Length 80 Set between 100 ft. and 180 ft. ft. and ft. Gravel pack? Yes Size range of material 1/2 down		
Fine sand		46	75	11. Static water level: mo./day/yr. 107 ft. below land surface Date 6-26-76		
Brown clay		75	82	12. Pumping level below land surfaces: 170 ft. after 2 hrs. pumping 1120 g.p.m. Estimated maximum yield 1120 g.p.m.		
Med. sand and gravel		82	94	13. Water sample submitted: mo./day/yr. Yes <input checked="" type="checkbox"/> No Date		
Clay		94	100	14. Well head completion: Pitless adapter <input checked="" type="checkbox"/> Inches above grade		
Good med. sand and gravel		100	135	15. Well grouted? Yes With: Neat cement Bentonite <input checked="" type="checkbox"/> Concrete Depth: From 0 ft. to 10 ft.		
Extra good sand and gravel		135	145	16. Nearest source of possible contamination: NA ft. Direction Type Well disinfected upon completion? Yes <input checked="" type="checkbox"/> No		
Brown coliche clay		145	158	17. Pump: Not installed Manufacturer's name Gouids Model number 12JMHC HP 125 Volts Length of drop pipe 165 ft. capacity 1000 p.m. Type: <input checked="" type="checkbox"/> Submersible <input checked="" type="checkbox"/> Turbine <input type="checkbox"/> Jet <input type="checkbox"/> Reciprocating <input type="checkbox"/> Centrifugal <input type="checkbox"/> Other		
(Use a second sheet if needed)						
18. Elevation:	19. Remarks:		20. Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. Ace-Hi International 190 Business name License No. Address Dodge City, Kansas Signed Carl G. Little Date 7-29-76 Authorized representative			
Topography: <input type="checkbox"/> Hill <input type="checkbox"/> Slope <input checked="" type="checkbox"/> Upland <input type="checkbox"/> Valley						

Forward the white, blue and pink copies to the Department of Health and Environment

Form WWC-5