

WATER WELL RECORD Form WWC-5 KSA 82a-1212

| | | | | |
|---------------------------|----------------------|----------------|-----------------|--------------|
| 1 LOCATION OF WATER WELL: | Fraction | Section Number | Township Number | Range Number |
| COUNTY: 029 FORD | SE 1/4 NW 1/4 NW 1/4 | 07 | T 27 S | R 24 W |

Distance and direction from nearest town or city street address of well if located within city?
 FROM DODGE CITY; APPX 1 MILE SOUTH

2 WATER WELL OWNER: LOREN DOLL, INC.
 RR#, St. Address, Box # : 214 E FRONTVIEW SUITE B Board of Agriculture, Division of Water Resources
 City, State, ZIP code : DODGE CITY, KS 67801-2204 Application Number: 45,872

3 LOCATE WELL'S LOCATION WITH
 AN "X" IN SECTION BOX:

| | | | | |
|-----|------|--|----|---|
| / \ | | | | |
| 1 | X NW | | NE | |
| M | | | | |
| i | W | | | E |
| l | | | | |
| e | | | | |
| | SW | | SE | |
| \ / | | | | |

4 DEPTH OF COMPLETED WELL 177 ELEVATION: 0
 Depth(s) Groundwater Encountered 1. 0 ft. 2. 0 ft. 3. 0 ft.

WELL'S STATIC WATER LEVEL 55 ft. below land surface measured on mo/day/yr 06/30/04
 Pump test data: Well water was 0 ft. after 0 hours pumping 0 gpm

Estimated Yield 0 gpm: Well water was 0 ft. after 0 hours pumping 0 gpm

Bore Hole Diameter 11 in. to 180 ft., and in. to 0 ft.

WELL WATER TO BE USED AS: 03 FEEDLOT

Was a chemical/bacteriological sample submitted to department? No ;
 If yes, mo/day/yr sample was submitted Water well disinfected? Yes

5 TYPE OF BLANK CASING USED: 02 PVC CASING JOINTS: GLUED
 Blank casing diameter 6 in. to 177 ft., Dia in. to 0 ft., Dia in. to 0 ft.
 Casing height above land surface 12 in., weight 4 lbs/ft. Wall thickness or gauge No. .316
 TYPE OF SCREEN OR PERFORATION MATERIAL: 07 PVC
 SCREEN OR PERFORATION OPENINGS ARE: 03 MILL SLOT

| | | |
|------------------------------|--------------------------|---------------------|
| SCREEN PERFORATED INTERVALS: | From 117 ft. to 157 ft., | From 0 ft. to 0 ft. |
| | From 0 ft. to 0 ft., | From 0 ft. to 0 ft. |
| GRAVEL PACK INTERVALS: | From 25 ft. to 180 ft., | From 0 ft. to 0 ft. |
| | From 0 ft. to 0 ft., | From 0 ft. to 0 ft. |

6 GROUT MATERIAL 03 BENTONITE
 Grout Intervals: From 5 ft. to 25 ft., From 60 ft. to 70 ft., From 0 ft. to 0 ft.
 What is the nearest source of possible contamination: NONE OBSERVED
 Direction from well? How many feet? 0

| FROM | TO | LITHOLOGIC LOG | FROM | TO | PLUGGING INTERVALS |
|------|-----|----------------------------|------|----|--------------------|
| 0 | 1 | 02 SILT | | | |
| 1 | 7 | 07 FINE SAND | | | |
| 7 | 42 | 05 SAND 11 GRAVEL 01 CLAY | | | |
| 42 | 48 | 04 SANDY CLAY | | | |
| 48 | 58 | 05 SAND 13 FINE GRAVEL | | | |
| 58 | 70 | 04 SANDY CLAY 20 LIMESTONE | | | |
| 70 | 86 | 05 SAND | | | |
| 86 | 90 | 04 SANDY CLAY | | | |
| 90 | 103 | 05 SAND | | | |
| 103 | 104 | 04 SANDY CLAY | | | |

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 06/16/04 and this record is true to the best of my knowledge and belief. Kansas
 Water Well Contractor's License No. 145 This Water Well Record was completed on (mo/day/yr) 08/31/04
 under the business name of HENKLE DRILLING & SUPPLY by (signature)

RECEIVED
 SEP 20 2004
 BUREAU OF WATER

(Continued)

WATER WELL RECORD Form WWC-5 KSA 82a-1212

| | | | | |
|---|----------------------------------|----------------------|---------------------------|------------------------|
| 1 LOCATION OF WATER WELL: COUNTY: 029 FORD | Fraction SE 1/4 NW 1/4 NW 1/4 | Section Number 07 | Township Number T 27 S | Range Number R 24 W |
|---|----------------------------------|----------------------|---------------------------|------------------------|

| | | |
|---|--|---|
| 2 WATER WELL OWNER: RR#, St. Address, Box # : City, State, ZIP code : | LOREN DOLL, INC. 214 E FRONTVIEW SUITE B DODGE CITY, KS 67801-2204 | Board of Agriculture, Division of Water Resources Application Number: 45,872 |
|---|--|---|

| FROM | TO | LITHOLOGIC LOG |
|------|-----|-----------------|
| 104 | 126 | 05 SAND |
| 126 | 131 | 04 SANDY CLAY |
| 131 | 157 | 05 SAND 28 ROCK |
| 157 | 180 | 19 SHALE |

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 06/16/04 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 145 This Water Well Record was completed on (mo/day/yr) 08/31/04 under the business name of HENKLE DRILLING & SUPPLY by (signature)