

WATER WELL RECORD Form WWC-5 KSA 82a-1212

1 LOCATION OF WATER WELL: Fraction Section Number Township Number Range Number
 COUNTY: FORD SW 1/4 SW 1/4 NE 1/4 10 T 27 S R 24 W

Distance and direction from nearest town or city street address of well if located within city?

11643 E. MAIN ROAD DODGE CITY, KS 67801-

2 WATER WELL OWNER: RAMIREZ, FRANCISCO

RR#, St. Address, Box #: 11643 E. MAIN ROAD

City, State, ZIP code : DODGE CITY, KS 67801-

Board of Agriculture, Division of Water Resources

Application Number:

3 LOCATE WELL'S LOCATION WITH
 AN "X" IN SECTION BOX:

1	2	3	4
5	6	7	8
9	10	11	12
13	14	15	16

WELL'S LOCATION: X

4 DEPTH OF COMPLETED WELL 145 ELEVATION: 0
 Depth(s) Groundwater Encountered 1. 0 ft. 2. 0 ft. 3. 0 ft.

WELL'S STATIC WATER LEVEL 34 ft. below land surface measured on mo/day/yr 06/17/04

Pump test data: Well water was 0 ft. after 0 hours pumping 0 gpm

Estimated Yield 40 gpm: Well water was 0 ft. after 0 hours pumping 0 gpm

Bore Hole Diameter 9 in. to 145 ft., and in. to 0 ft.

WELL WATER TO BE USED AS: DOMESTIC

Was a chemical/bacteriological sample submitted to department? No ;

If yes, mo/day/yr sample was submitted Water well disinfected? Yes

5 TYPE OF BLANK CASING USED: PVC

CASING JOINTS: GLUED

Blank casing diameter 5 in. to 145 ft., Dia in. to 0 ft., Dia in. to 0 ft.

Casing height above land surface 12 in., weight 200 lbs/ft. Wall thickness or gauge No. 21

TYPE OF SCREEN OR PERFORATION MATERIAL: PVC

SCREEN OR PERFORATION OPENINGS ARE: SAW CUT

SCREEN PERFORATED INTERVALS: From 120 ft. to 140 ft., From 0 ft. to 0 ft.

From 0 ft. to 0 ft., From 0 ft. to 0 ft.

GRAVEL PACK INTERVALS: From 20 ft. to 40 ft., From 0 ft. to 0 ft.

From 62 ft. to 145 ft., From 0 ft. to 0 ft.

6 GROUT MATERIAL BENTONITE

Grout Intervals: From 5 ft. to 20 ft., From 40 ft. to 62 ft., From 0 ft. to 0 ft.

What is the nearest source of possible contamination: LIVESTOCK PENS

Direction from well? SOUTH

How many feet? 70

FROM	TO	LITHOLOGIC LOG
0	20	01 TOPSOIL 10 FINE-MEDSAND 05 CLAY
20	40	05 CLAY 37 FIN-COAR SAN 05 CLAY
40	60	05 CLAY
60	80	05 CLAY 37 FIN-COAR SAN
80	120	37 FIN-COAR SAN 06 SMALL GRAVEL
120	145	37 FIN-COAR SAN 38 SMAL-MED GRA
145	160	05 CLAY 07 BLUE SHALE

FROM	TO	PLUGGING INTERVALS
RECEIVED		
OCT 27 2004		
BUREAU OF WATER		

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 06/19/04 and this record is true to the best of my knowledge and belief. Kansas

Water Well Contractor's License No. 179

This Water Well Record was completed on (mo/day/yr) 06/24/04

under the business name of JOE'S WELL SERVICE, INC.

by (signature) *Josiah Crick*