

1 LOCATION OF WATER WELL: Fraction Section Number Township Number Range Number  
 COUNTY: FORD NW 1/4 NW 1/4 NW 1/4 3 T 27 S R 24 W

Distance and direction from nearest town or city street address of well if located within city?  
 11508 W. MAIN ROAD WILROADS GARDEN, KS 67801-

2 WATER WELL OWNER: URBAN, JOE  
 RR#, St. Address, Box #: 11656 E. MAIN ROAD Board of Agriculture, Division of Water Resources  
 City, State, ZIP code: DODGE CITY, KS 67801- Application Number:

3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX:

	X		

4 DEPTH OF-COMPLETED WELL 160 ELEVATION: 0  
 Depth(s) Groundwater Encountered 1. 0 ft. 2. 0 ft. 3. 0 ft.

WELL'S STATIC WATER LEVEL 30 ft. below land surface measured on mo/day/yr 11/23/04  
 Pump testdata: Well water was 0 ft. after 0 hours pumping 0 gpm

Estimated Yield 50 gpm: Well water was 0 ft. after 0 hours pumping 0 gpm

Bore Hole Diameter 9 in. to 160 ft., and in. to 0 ft.

WELL WATER TO BE USED AS: DOMESTIC

Was a chemical/bacteriological sample submitted to department? No ;

If yes, mo/day/yr sample was submitted

Water well disinfected? Yes

5 TYPE OF BLANK CASING USED: PVC

CASING JOINTS: GLUED

Blank casing diameter 5 in. to 160 ft., Dia in. to 0 ft., Dia in. to 0 ft.  
 Casing height above land surface 12 in., weight 200 lbs/ft. Wall thickness or gauge No. 21

TYPE OF SCREEN OR PERFORATION MATERIAL: PVC

SCREEN OR PERFORATION OPENINGS ARE: SAW CUT

SCREEN PERFORATED INTERVALS: From 140 ft. to 160 ft., From 0 ft. to 0 ft.

From 0 ft. to 0 ft., From 0 ft. to 0 ft.

GRAVEL PACK INTERVALS: From 80 ft. to 160 ft., From 0 ft. to 0 ft.

From 0 ft. to 0 ft., From 0 ft. to 0 ft.

6 GROUT MATERIAL BENTONITE

Grout Intervals: From 5 ft. to 80 ft., From 0 ft. to 0 ft., From 0 ft. to 0 ft.

What is the nearest source of possible contamination: NONE

Direction from well?

How many feet? 0

FROM	TO	LITHOLOGIC LOG
0	20	01 TOPSOIL 37 FIN-COAR SAN 09 GRAVEL
20	30	37 FIN-COAR SAN 09 GRAVEL 05 CLAY
30	40	05 CLAY
40	80	10 FINE-MEDSAND 05 CLAY
80	90	05 CLAY
90	120	37 FIN-COAR SAN
120	150	37 FIN-COAR SAN 06 SMALL GRAVEL
150	160	05 CLAY 07 BLUE SHALE

FROM	TO	PLUGGING INTERVALS

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 11/24/04 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 179 This Water Well Record was completed on (mo/day/yr) 11/29/04 under the business name of JOE'S WELL SERVICE, INC. by (signature) *Justin Creek*