

## WATER WELL RECORD Form WWC-5 KSA 82a-1212

1 LOCATION OF WATER WELL: Fraction Section Number Township Number Range Number  
 COUNTY: FORD NW 1/4 NW 1/4 NW 1/4 5 T 27 S R 24 W

Distance and direction from nearest town or city street address of well if located within city?  
 GREEN ACRES TRAILER PARK

2 WATER WELL OWNER: RODRIGUEZ, ABIGEL  
 RR#, St. Address, Box #: 11357 EL TORO Board of Agriculture, Division of Water Resources  
 City, State, ZIP code: DODGE CITY, KS 67801- Application Number:

3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX:

1	2	3	4
W			E
SW			SE

4 DEPTH OF COMPLETED WELL 165 ELEVATION: 0  
 Depth(s) Groundwater Encountered 1. 0 ft. 2. 0 ft. 3. 0 ft.

WELL'S STATIC WATER LEVEL 40 ft. below land surface measured on mo/day/yr 03/20/11  
 Pump test data: Well water was 0 ft. after 0 hours pumping 0 gpm

Estimated Yield 65 gpm: Well water was 0 ft. after 0 hours pumping 0 gpm

Bore Hole Diameter 9 in. to 165 ft., and in. to 0 ft.

WELL WATER TO BE USED AS: DOMESTIC

Was a chemical/bacteriological sample submitted to department? No;  
 If yes, mo/day/yr sample was submitted Water well disinfected? Yes

5 TYPE OF BLANK CASING USED: CERTA LOC CASIN CASING JOINTS: CERTA-LOC  
 Blank casing diameter 5 in. to 165 ft., Dia in. to 0 ft., Dia in. to 0 ft.  
 Casing height above land surface 12 in., weight 200 lbs/ft. Wall thickness or gauge No. 21  
 TYPE OF SCREEN OR PERFORATION MATERIAL: PVC  
 SCREEN OR PERFORATION OPENINGS ARE: SAW CUT

SCREEN PERFORATED INTERVALS: From 120 ft. to 160 ft., From 0 ft. to 0 ft.  
 From 0 ft. to 0 ft., From 0 ft. to 0 ft.

GRAVEL PACK INTERVALS: From 35 ft. to 165 ft., From 0 ft. to 0 ft.  
 From 0 ft. to 0 ft., From 0 ft. to 0 ft.

6 GROUT MATERIAL BENTONITE  
 Grout intervals: From 6 ft. to 35 ft., From 0 ft. to 0 ft., From 0 ft. to 0 ft.  
 What is the nearest source of possible contamination: NONE  
 Direction from well? How many feet? 0

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	20	01 TOPSOIL 02 FINE SAND 05 CLAY			
20	40	04 COARSE SAND 05 CLAY			
40	60	05 CLAY			
60	80	05 CLAY 10 FINE-MEDSAND 19 LAYERS			
80	100	02 FINE SAND			
100	120	37 FIN-COAR SAN			
120	140	37 FIN-COAR SAN 06 SHALL GRAVEL			
140	160	37 FIN-COAR SAN 38 SHAL-MED GRA			
160	180	05 CLAY 07 BLUE SHALE			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 03/21/11 and this record is true to the best of my knowledge and belief. Kansas  
 Water Well Contractor's License No. 179 This Water Well Record was completed on (mo/day/yr) 04/08/11  
 under the business name of JOE'S WELL SERVICE, INC. by (signature) Judith Creek