

WATER WELL RECORD

Form WWC-5

Division of Water Resources App. No.

22,394

1 LOCATION OF WATER WELL: County: FORD		Fraction ¼ SE ¼ SE ¼ NW ¼		Section Number 13		Township No. T 28 S		Range Number R 24 ☐ E ☒ W										
Street/Rural Address of Well Location; if unknown, distance & direction from nearest town or intersection: If at owner's address, check here ☐ FORT DODGE - 2 MILES SE ON HWY.54, 7-3/4 MILES S., 2,788 FT. N. & 2,736 FT. W.				Global Positioning System (GPS) information: Latitude: (in decimal degrees) Longitude: (in decimal degrees) Elevation: Datum: ☐ WGS 84, ☐ NAD 83, ☐ NAD 27 Collection Method: ☐ GPS unit (Make/Model:) ☐ Digital Map/Photo, ☐ Topographic Map, ☐ Land Survey Est. Accuracy: ☐ <3 m, ☐ 3-5 m, ☐ 5-15 m, ☐ >15 m														
2 WATER WELL OWNER: DAVID L. & CAROL R. WARE RR#, Street Address, Box #: 13469 W. LINKS AVE. City, State, ZIP Code : WICHITA, KANSAS 67235																		
3 LOCATE WELL WITH AN "X" IN SECTION BOX: N <table border="1" style="margin: auto;"> <tr><td> </td><td> </td><td> </td></tr> <tr><td>-- NW --</td><td style="text-align: center;">X</td><td>-- NE --</td></tr> <tr><td>-- SW --</td><td> </td><td>-- SE --</td></tr> </table> S -----1 mile-----					-- NW --	X	-- NE --	-- SW --		-- SE --	4 DEPTH OF COMPLETED WELL 350 ft. Depth(s) Groundwater Encountered (1) ft. (2) ft. (3) ft. WELL'S STATIC WATER LEVEL 145 ft. below land surface measured on mo/day/yr. 5-19-11 Pump test data: Well water was ft. after hours pumping gpm EST. YIELD gpm. Well water was ft. after hours pumping gpm Bore Hole Diameter 30 in. to 350 ft., and in. to ft. WELL WATER TO BE USED AS: ☐ Public water supply ☐ Geothermal ☐ Injection well ☐ Domestic ☐ Feedlot ☐ Oil field water supply ☐ Dewatering ☐ Other (Specify below) ☒ Irrigation ☐ Industrial ☐ Domestic-lawn & garden ☐ Monitoring well Was a chemical/bacteriological sample submitted to Department? ☐ Yes ☒ No If yes, mo/day/yr sample was submitted Water well disinfected? ☐ Yes ☒ No							
-- NW --	X	-- NE --																
-- SW --		-- SE --																
5 TYPE OF CASING USED: ☒ Steel ☐ PVC ☐ Other CASING JOINTS: ☐ Glued ☐ Clamped ☒ Welded ☐ Threaded Casing diameter 16 in. to 200 ft., Diameter in. to ft., Diameter in. to ft. Casing height above land surface 12 in., Weight 42.05 lbs./ft., Wall thickness or gauge No. 250 TYPE OF SCREEN OR PERFORATION MATERIAL: ☒ Steel ☐ Stainless Steel ☐ PVC ☐ Other (Specify) ☐ Brass ☐ Galvanized Steel ☐ None used (open hole) SCREEN OR PERFORATION OPENINGS ARE: ☐ Continuous slot ☒ Mill slot ☐ Gauze wrapped ☐ Torch cut ☐ Drilled holes ☐ None (open hole) ☐ Louvered shutter ☐ Key punched ☒ Wire wrapped ☐ Saw cut ☐ Other (specify) SCREEN-PERFORATED INTERVALS: From 200 ft. to 350 ft., From ft. to ft. From ft. to ft., From ft. to ft. GRAVEL PACK INTERVALS: From 20 ft. to 350 ft., From ft. to ft. From ft. to ft., From ft. to ft.																		
6 GROUT MATERIAL: ☐ Neat cement ☒ Cement grout ☐ Bentonite ☐ Other Grout Intervals: From 0 ft. to 20 ft., From ft. to ft., From ft. to ft. What is the nearest source of possible contamination: ☐ Septic tank ☐ Lateral lines ☐ Pit privy ☐ Livestock pens ☐ Insecticide storage ☐ Other (specify below) ☐ Sewer lines ☐ Cesspool ☐ Sewage lagoon ☐ Fuel storage ☐ Abandoned water well ☐ Watertight sewer lines ☐ Seepage pit ☐ Feedyard ☐ Fertilizer storage ☐ Oil well/gas well N/A Direction from well Distance from well																		
FROM	TO	LITHOLOGIC LOG		FROM	TO	LITHO. LOG (cont.) or PLUGGING INTERVALS												
0	20	Top soil & clay		240	260	Fine coarse sand-small gravel												
20	120	Tan clay		260	280	Fine coarse sand-small gravel												
120	140	Fine coarse sand		280	300	Fine medium sand-clay												
140	165	Fine coarse sand-small medium gravel				- fine coarse sand												
165	180	White clay		300	318	Fine coarse sand-small gravel												
180	200	White clay-fine medium sand in layers		318	340	Clay-Thin rock layers (fine sand)												
				340	360	Gray clay												
				360	380	Gray clay												
200	220	Fine medium sand		380	400	Blue shale												
220	240	Fine medium sand																
7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was ☒ constructed, ☐ reconstructed, or ☐ plugged under my jurisdiction and was completed on (mo/day/year) 5-19-11 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 208 This Water Well Record was completed on (mo/day/year) 5-24-11 under the business name of MINTER-WILSON DRILLING CO., INC. by (signature) <i>Nna Keller</i>																		
INSTRUCTIONS: Use typewriter or ball point pen. <u>PLEASE PRESS FIRMLY</u> and <u>PRINT</u> clearly. Please fill in blanks and check the correct answers. Send three copies (white, blue, pink) to Kansas Department of Health and Environment, Bureau of Water, Geology Section, 1000 SW Jackson St., Suite 420, Topeka, Kansas 66612-1367. Telephone 785-296-5522. Send one copy to WATER WELL OWNER and retain one for your records. Include fee of \$5.00 for each constructed well. Visit us at http://www.kdheks.gov/waterwell/index.html .																		