

1 LOCATION OF WATER WELL:		Fraction		Section Number		Township Number		Range Number	
County: Ford		SE ¼ SE ¼ SE ¼		17		T 27 S		R 24 EW	
Distance and direction from nearest town or city street address of well if located within city? ~100' N, 100' E of Primrose & 114th Rds									
2 WATER WELL OWNER: Cargill									
RR#, St. Address, Box # : PO Box 1060					Board of Agriculture, Division of Water Resources				
City, State, ZIP Code : Dodge City, Kansas 67801					Application Number:				
3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX: N NW NE SW SE S W E X			4 DEPTH OF COMPLETED WELL 135.35 ft ELEVATION:						
			Depth(s) Groundwater Encountered 1. ft 2. ft 3. ft WELL'S STATIC WATER LEVEL ft below land surface measured on mo/day/yr Pump test data: Well water was NA ft. after hours pumping gpm Est. Yield NA gpm: Well water was ft. after hours pumping gpm Bore Hole Diameter 6.25 in. to 141 ft, and in. to ft WELL WATER TO BE USED AS: 5 Public water supply 8 Air conditioning 11 Injection well 1 Domestic 3 Feedlot 6 Oil field water supply 9 Dewatering 12 Other (Specify below) 2 Irrigation 4 Industrial 7 Lawn and garden only 10 Monitoring well Was a chemical/bacteriological sample submitted to Department? Yes ☐ No ☒ If yes, mo/day/yr sample was submitted Water Well Disinfected? Yes ☐ No ☒						
5 TYPE OF BLANK CASING USED:									
1 Steel 3 RMP (SR) 5 Wrought iron 8 Concrete tile			CASING JOINTS: Glued Clamped						
2 PVC 4 ABS 6 Asbestos-Cement 9 Other (specify below)			Welded						
Blank casing diameter 2 in. to 115.01 ft, Dia 2 in. to 135.35 ft, Dia in. to ft			Threaded ☒						
Casing height above land surface 2.7 in., weight lbs./ft. Wall thickness or gauge No. Sch. 40									
TYPE OF SCREEN OR PERFORATION MATERIAL									
1 Steel 3 Stainless steel 5 Fiberglass 7 PVC 10 Asbestos-cement									
2 Brass 4 Galvanized steel 6 Concrete tile 8 RMP (SR) 11 Other (specify)									
SCREEN OR PERFORATION OPENINGS ARE:			12 None used (open hole)						
1 Continuous slot 3 Mill slot 5 Gauzed wrapped 8 Saw cut 11 None (open hole)									
2 Louvered shutter 4 Key punched 6 Wire wrapped 9 Drilled holes									
SCREEN-PERFORATED INTERVALS: From 115.01 ft to 135.01 ft, From ft to ft									
GRAVEL PACK INTERVALS: From 113 ft to 141 ft, From ft to ft									
From ft to ft, From ft to ft									
6 GROUT MATERIAL: 1 Neat cement 2 Cement grout 3 Bentonite 4 Other Concrete									
Grout intervals: From 0 ft to 0.5 ft, From 0.5 ft to 115 ft, From ft to ft									
What is the nearest source of possible contamination:									
1 Septic tank 4 Lateral lines 7 Pit privy 10 Livestock pens 14 Abandoned water well									
2 Sewer lines 5 Cess pool 8 Sewage lagoon 11 Fuel storage 15 Oil well/Gas well									
3 Watertight sewer lines 6 Seepage pit 9 Feedyard 12 Fertilizer storage 16 Other (specify below)									
Direction from well? How many feet?									
FROM TO LITHOLOGIC LOG FROM TO PLUGGING INTERVALS									
0	14	Clay, tr. to some silt, Brown	120	124	Sand, f-c, tr. f gravel, Lt. Brown				
14	16	Clay, some silt, tr. f sand, Brown	124	133	Sand, f-tr. m, Lt. Brown				
16	24	Sand, m, tr. clay, Lt. Brown	133	138	Gravel, f-m, w/m-c sand, Lt. Brown				
24	26	Clay, w/f sand, Brown	138	141	Sand, f-m, tr. f gravel, Lt. Brown				
26	32	Sand, f-m, poss. clay interbeds, Lt. Brown							
32	50	Sand, f-m, Lt. Brown							
50	57	Sand, f-m, tr. clay, Lt. Brown							
57	68	Sand, f-tr. c, tr. clay, Lt. Brown							
68	75	Sand, f-tr. c, tr. clay, tr. f gravel, Lt. Brown							
75	86	Sand, m-c, w/f gravel, Lt. Brown							
86	93	Sand, m-c, w/f-tr. m gravel, Lt. Brown							
93	104	Sand, f-m w/tr. c, Lt. Brown							
104	108	Sand, f-some m, Lt. Brown			IR-4R, Abovegrade				
108	112	Sand, m-tr. c, Lt. Brown							
112	120	Sand, f-tr. m, Lt. Brown							
7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was (1) constructed, (2) reconstructed, or (3) plugged under my jurisdiction and was completed on (mo/day/year) 5/6/2014 and this record is true to the best of my knowledge and belief.									
Kansas Water Well Contractor's License No. 527 This Water Well Record was completed on (mo/day/yr) 5/30/14									
under the business name of GeoCore, Inc. by (signature) <i>Dale R. H.</i>									