

1 LOCATION OF WATER WELL:		Fraction	Section Number	Township Number	Range Number
COUNTY: FORD		SW 1/4 SW 1/4 NW 1/4	18	T 27 S	R 25 W
Distance and direction from nearest town or city street address of well if located within city? FROM DODGE CITY ON HIGHWAY 56 - 5 WEST AND 1 SOUTH					
2 WATER WELL OWNER:		Board of Agriculture, Division of Water Resources			
RR#, St. Address, Box #: TURLEY, BILL 1214 LONGBRANCH		Application Number:			
City, State, ZIP code : DODGE CITY, KS 67801-					
3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX:		4 DEPTH OF COMPLETED WELL 247 ELEVATION: 0			
		Depth(s) Groundwater Encountered 1. 0 ft. 2. 0 ft. 3. 0 ft.			
WELL'S STATIC WATER LEVEL 138 ft. below land surface measured on mo/day/yr 04/19/95					
Pump test data: Well water was 0 ft. after 0 hours pumping 0 gpm					
Estimated Yield 35 gpm: Well water was 0 ft. after 0 hours pumping 0 gpm					
Bore Hole Diameter 9 in. to 247 ft., and in. to 0 ft.					
WELL WATER TO BE USED AS: DOMESTIC					
Was a chemical/bacteriological sample submitted to department? No ;					
If yes, mo/day/yr sample was submitted		Water well disinfected? Yes			
5 TYPE OF BLANK CASING USED: PVC		CASING JOINTS: GLUED			
Blank casing diameter 5 in. to 247 ft., Dia in. to 0 ft., Dia in. to 0 ft.					
Casing height above land surface 12 in., weight 200 lbs/ft. Wall thickness or gauge No. 21					
TYPE OF SCREEN OR PERFORATION MATERIAL: PVC					
SCREEN OR PERFORATION OPENINGS ARE: SAW CUT					
SCREEN PERFORATED INTERVALS:		From 200 ft. to 240 ft., From 0 ft. to 0 ft.			
GRAVEL PACK INTERVALS:		From 0 ft. to 0 ft., From 0 ft. to 0 ft.			
		From 40 ft. to 247 ft., From 0 ft. to 0 ft.			
		From 0 ft. to 0 ft., From 0 ft. to 0 ft.			
6 GROUT MATERIAL BENTONITE					
Grout intervals: From 0 ft. to 40 ft., From 0 ft. to 0 ft., From 0 ft. to 0 ft.					
What is the nearest source of possible contamination: ABANDONED WELL		How many feet? 10			
Direction from well? SOUTH					
FROM	TO	LITHOLOGIC LOG		FROM	TO
0	20	TOPSOIL SANDY BROWN CLAY			
20	85	FINE SAND			
85	90	BROWN CLAY			
90	94	FINE SAND			
94	100	BROWN CLAY			
100	160	MEDIUM SAND GRAVEL			
160	168	BROWN CLAY			
168	170	FINE SAND			
170	195	SANDY BROWN CLAY			
195	215	MEDIUM SAND GRAVEL			
7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 04/20/95 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 179 This Water Well Record was completed on (mo/day/yr) 05/11/95 under the business name of JOE'S WELL SERVICE, INC. by (signature) <i>Joe's Well Service</i>					

(Continued)

1 LOCATION OF WATER WELL:		Fraction	Section Number	Township Number	Range Number
COUNTY: FORD		SW 1/4 SW 1/4 NW 1/4	18	T 27 S	R 25 W
2 WATER WELL OWNER:		Board of Agriculture, Division of Water Resources			
RR#, St. Address, Box #: TURLEY, BILL 1214 LONGBRANCH		Application Number:			
City, State, ZIP code : DODGE CITY, KS 67801-					
FROM	TO	LITHOLOGIC LOG			
215	220	BROWN CLAY			
220	240	BROWN CLAY ROCK GRAVEL			
240	260	RIMP SHALE			