

1 LOCATION OF WATER WELL: Fraction Section Number Township Number Range Number
 COUNTY: PORD NW 1/4 NW 1/4 NW 1/4 9 T 27 S R 25 W

Distance and direction from nearest town or city street address of well if located within city?
 FROM DODGE CITY - JCT 283 & 56 3 MILES WEST AND 1/4 SOUTH

2 WATER WELL OWNER: EDWARDS, PHIL
 RR#, St. Address, Box #: 108 CHAPPERAL CIRCLE DR. Board of Agriculture, Division of Water Resources
 City, State, ZIP code : DODGE CITY, KS 67801- Application Number:

3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX:

1	2	3	4	5	6	7	8
	NW			NE			
W					E		
	SW			SE			
	X						

4 DEPTH OF COMPLETED WELL 165 ELEVATION: 0
 Depth(s) Groundwater Encountered 1. 0 ft. 2. 0 ft. 3. 0 ft.

WELL'S STATIC WATER LEVEL 74 ft. below land surface measured on no/day/yr 02/23/95
 Pump testdata: Well water was 0 ft. after 0 hours pumping 0 gpm
 Estimated Yield 50 gpm: Well water was 0 ft. after 0 hours pumping 0 gpm
 Bore Hole Diameter 9 in. to 165 ft., and in. to 0 ft.
 WELL WATER TO BE USED AS: DOMESTIC
 Was a chemical/bacteriological sample submitted to department? No;
 If yes, no/day/yr sample was submitted Water well disinfected? Yes

5 TYPE OF BLANK CASING USED: PVC CASING JOINTS: GLUED
 Blank casing diameter 5 in. to 165 ft., Dia in. to 0 ft., Dia in. to 0 ft.
 Casing height above land surface 12 in., weight 200 lbs/ft. Wall thickness or gauge No. 21
 TYPE OF SCREEN OR PERFORATION MATERIAL: PVC
 SCREEN OR PERFORATION OPENINGS ARE: SAW CUT

SCREEN PERFORATED INTERVALS: From 130 ft. to 160 ft., From 0 ft. to 0 ft.
 From 0 ft. to 0 ft., From 0 ft. to 0 ft.
 GRAVEL PACK INTERVALS: From 42 ft. to 165 ft., From 0 ft. to 0 ft.
 From 0 ft. to 0 ft., From 0 ft. to 0 ft.

6 GROUT MATERIAL BENTONITE
 Grout Intervals: From 0 ft. to 42 ft., From 0 ft. to 0 ft., From 0 ft. to 0 ft.
 What is the nearest source of possible contamination: NONE - NEW SITE
 Direction from well? How many feet? 0

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	20	TOPSOIL CLAY			
20	35	SAND CLAY			
35	120	FINE - MED SAND GRAVEL			
120	155	MED-COARSE SAND GRAVEL			
155	190	YELLOW CLAY			
190	200	BLUE SHALE			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (no/day/year) 07/15/95 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 179 This Water Well Record was completed on (no/day/yr) 08/01/95 under the business name of JOB'S WELL SERVICE, INC. by (signature) *Justin Cuck*