

1 LOCATION OF WATER WELL:		Fraction	Section Number	Township Number	Range Number
COUNTY: FORD		NW 1/4 NE 1/4 NW 1/4	36	T 27 S	R 25 E

Distance and direction from nearest town or city street address of well if located within city?
 FROM DODGE CITY - 4 SOUTH OF 156 & 283 - 1/4 E ON RIDGE RD

2 WATER WELL OWNER:		DENTON, JACK	
RR#, St. Address, Box # :		1901 BURR PARKWAY	
City, State, ZIP code :		DODGE CITY, KS 67801-	
		Board of Agriculture, Division of Water Resources Application Number:	

3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX:		4 DEPTH OF COMPLETED WELL 225 ELEVATION: 0							
<table border="1"> <tr> <td>1</td> <td>NW</td> <td>NE</td> </tr> <tr> <td>2</td> <td>SW</td> <td>SE</td> </tr> </table>		1	NW	NE	2	SW	SE	Depth(s) Groundwater Encountered 1. 0 ft. 2. 0 ft. 3. 0 ft. WELL'S STATIC WATER LEVEL 129 ft. below land surface measured on mo/day/yr 11/05/96 Pump test data: Well water was 0 ft. after 0 hours pumping 0 gpm Estimated Yield 40 gpm: Well water was 0 ft. after 0 hours pumping 0 gpm Bore Hole Diameter 10 in. to 225 ft. and in. to 0 ft. WELL WATER TO BE USED AS: DOMESTIC Was a chemical/bacteriological sample submitted to department? No ; If yes, mo/day/yr sample was submitted Water well disinfected? Yes	
1	NW	NE							
2	SW	SE							

5 TYPE OF BLANK CASING USED: PVC		CASING JOINTS: GLUED	
Blank casing diameter 5 in. to 225 ft., Dia in. to 0 ft., Dia in. to 0 ft.		Casing height above land surface 12 in., weight 200 lbs/ft. Wall thickness or gauge No. 21	
TYPE OF SCREEN OR PERFORATION MATERIAL: PVC			
SCREEN OR PERFORATION OPENINGS ARE: SAW CUT			

SCREEN PERFORATED INTERVALS:		FROM 180 ft. to 220 ft., FROM 0 ft. to 0 ft.	
GRAVEL PACK INTERVALS:		FROM 0 ft. to 0 ft., FROM 0 ft. to 0 ft.	

6 GROUT MATERIAL BENTONITE			
Grout Intervals: FROM 0 ft. to 33 ft., FROM 0 ft. to 0 ft., FROM 0 ft. to 0 ft.			
What is the nearest source of possible contamination: NONE - NEW SITE		How many feet? 0	
Direction from well?			

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	20	TOPSOIL CLAY			
20	60	CLAY TAN IN COLOR			
60	80	CLAY SANDSTONE FINE SAND			
80	100	FINE - MED SAND			
100	120	MED-COARSE SAND SMALL GRAVEL			
120	140	COARSE SAND SMALL GRAVEL			
140	160	COARSE SAND SMALL GRAVEL CLAY			
160	180	CLAY FINE SAND			
180	200	CLAY FINE SAND COARSE SAND			
200	220	CLAY FINE SAND COARSE SAND			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 01/30/97 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 179 This Water Well Record was completed on (mo/day/yr) 02/27/97 under the business name of JOE'S WELL SERVICE, INC. by (signature) <i>Joseph Creek</i>	
---	--

(Continued)

1 LOCATION OF WATER WELL:		Fraction	Section Number	Township Number	Range Number
COUNTY: FORD		NW 1/4 NE 1/4 NW 1/4	36	T 27 S	R 25 E

2 WATER WELL OWNER:		DENTON, JACK	
RR#, St. Address, Box # :		1901 BURR PARKWAY	
City, State, ZIP code :		DODGE CITY, KS 67801-	
		Board of Agriculture, Division of Water Resources Application Number:	

FROM	TO	LITHOLOGIC LOG
220	240	CLAY BLUE SHALE