

1 LOCATION OF WATER WELL: Fraction Section Number Township Number Range Number
 COUNTY: FORD NE 1/4 SW 1/4 NW 1/4 4 T 27 S R 25 E W

Distance and direction from nearest town or city street address of well if located within city?
 FROM DODGE CITY JCT. 283 & 56 - 21/2 W. HIGHWAY 56 - 1/4 S.

2 WATER WELL OWNER: CLYDE WADE
 RR#, St. Address, Box #: 2200 HART AVE.
 City, State, ZIP code: DODGE CITY, KS 67801- Board of Agriculture, Division of Water Resources
 Application Number:

3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX: 4 DEPTH OF COMPLETED WELL 157 ELEVATION: 0
 Depth(s) Groundwater Encountered 1. 0 ft. 2. 0 ft. 3. 0 ft.

WELL'S STATIC WATER LEVEL 80 ft. below land surface measured on mo/day/yr 10/29/97
 Pump test data: Well water was 0 ft. after 0 hours pumping 0 gpm
 Estimated Yield 85 gpm: Well water was 0 ft. after 0 hours pumping 0 gpm
 Bore Hole Diameter 10 in. to 157 ft., and in. to 0 ft.
 WELL WATER TO BE USED AS: DOMESTIC
 Was a chemical/bacteriological sample submitted to department? No;
 If yes, mo/day/yr sample was submitted Water well disinfected? Yes

5 TYPE OF BLANK CASING USED: PVC CASING JOINTS: GLUED
 Blank casing diameter 5 in. to 157 ft., Dia in. to 0 ft., Dia in. to 0 ft.
 Casing height above land surface 12 in., weight 200 lbs/ft. Wall thickness or gauge No. 21
 TYPE OF SCREEN OR PERFORATION MATERIAL: PVC
 SCREEN OR PERFORATION OPENINGS ARE: SAW CUT

SCREEN PERFORATED INTERVALS: From 112 ft. to 152 ft., From 0 ft. to 0 ft.
 From 0 ft. to 0 ft., From 0 ft. to 0 ft.
 GRAVEL PACK INTERVALS: From 30 ft. to 157 ft., From 0 ft. to 0 ft.
 From 0 ft. to 0 ft., From 0 ft. to 0 ft.

6 GROUT MATERIAL BENTONITE
 Grout Intervals: From 0 ft. to 30 ft., From 0 ft. to 0 ft., From 0 ft. to 0 ft.
 What is the nearest source of possible contamination: NONE - NEW SITE
 Direction from well? How many feet? 0

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	20	TOPSOIL FINE SAND			
20	40	FINE SAND CLAY FINE SAND			
40	60	FINE SAND COARSE SAND GRAVEL			
60	80	COARSE SAND SMALL GRAVEL			
80	145	COARSE SAND GRAVEL			
145	160	CLAY FINE SAND IN LAYERS			
160	180	CLAY			
180	200	CLAY BLUE SHALE			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 10/31/97 and this record is true to the best of my knowledge and belief. Kansas
 Water Well Contractor's License No. 179 This Water Well Record was completed on (mo/day/yr) 12/02/97
 under the business name of JOE'S WELL SERVICE, INC. by (signature) *Quaick Creek*