

WATER WELL RECORD Form WWC-5 KSA 82a-1212

1 LOCATION OF WATER WELL: COUNTY: FORD		Fraction SW 1/4 SE 1/4 SW 1/4	Section Number 36	Township Number T 27 S	Range Number R 25 W																																																																		
Distance and direction from nearest town or city street address of well if located within city? FROM DODGE CITY - JCT. 283 & 56 - 5 S. ON HIGHWAY 283 1/4 E.																																																																							
2 WATER WELL OWNER: RR#, St. Address, Box # : City, State, ZIP code :		GEUITZEN, TINA PHEASANT DRAW SUBDIVISION DODGE CITY, KS 67801-																																																																					
		Board of Agriculture, Division of Water Resources Application Number:																																																																					
3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX:		4 DEPTH OF COMPLETED WELL 205 ELEVATION: 0 Depth(s) Groundwater Encountered 1. 0 ft. 2. 0 ft. 3. 0 ft.																																																																					
<table border="1"> <tr> <td>1</td> <td>NW</td> <td>NE</td> </tr> <tr> <td>2</td> <td>SW</td> <td>SE</td> </tr> <tr> <td>3</td> <td>SW</td> <td>SE</td> </tr> </table>		1	NW	NE	2	SW	SE	3	SW	SE	WELL'S STATIC WATER LEVEL 146 ft. below land surface measured on mo/day/yr 04/16/98 Pump test data: Well water was 0 ft. after 0 hours pumping 0 gpm Estimated Yield 30 gpm: Well water was 0 ft. after 0 hours pumping 0 gpm Bore Hole Diameter 10 in. to 205 ft., and in. to 0 ft. WELL WATER TO BE USED AS: DOMESTIC Was a chemical/bacteriological sample submitted to department? No ; If yes, mo/day/yr sample was submitted Water well disinfected? Yes																																																												
1	NW	NE																																																																					
2	SW	SE																																																																					
3	SW	SE																																																																					
5 TYPE OF BLANK CASING USED: PVC CASING JOINTS: GLUED Blank casing diameter 5 in. to 205 ft., Dia. in. to 0 ft., Dia. in. to 0 ft. Casing height above land surface 12 in., weight 200 lbs/ft. Wall thickness or gauge No. 21 TYPE OF SCREEN OR PERFORATION MATERIAL: PVC SCREEN OR PERFORATION OPENINGS ARE: SAW CUT																																																																							
SCREEN PERFORATED INTERVALS: From 140 ft. to 200 ft., From 0 ft. to 0 ft. From 0 ft. to 0 ft., From 0 ft. to 0 ft. GRAVEL PACK INTERVALS: From 25 ft. to 205 ft., From 0 ft. to 0 ft. From 0 ft. to 0 ft., From 0 ft. to 0 ft.																																																																							
6 GROUT MATERIAL BENTONITE Grout Intervals: From 5 ft. to 25 ft., From 0 ft. to 0 ft., From 0 ft. to 0 ft. What is the nearest source of possible contamination: NONE - NEW SITE Direction from well? How many feet? 0																																																																							
<table border="1"> <thead> <tr> <th>FROM</th> <th>TO</th> <th>LITHOLOGIC LOG</th> <th>FROM</th> <th>TO</th> <th>PLUGGING INTERVALS</th> </tr> </thead> <tbody> <tr> <td>0</td> <td>20</td> <td>TOPSOIL CLAY</td> <td></td> <td></td> <td></td> </tr> <tr> <td>20</td> <td>40</td> <td>CLAY</td> <td></td> <td></td> <td></td> </tr> <tr> <td>40</td> <td>60</td> <td>CLAY FINE SAND</td> <td></td> <td></td> <td></td> </tr> <tr> <td>60</td> <td>100</td> <td>FINE SAND</td> <td></td> <td></td> <td></td> </tr> <tr> <td>100</td> <td>120</td> <td>FINE - MED SAND</td> <td></td> <td></td> <td></td> </tr> <tr> <td>120</td> <td>138</td> <td>FINE SAND COARSE SAND SMALL GRAVEL</td> <td></td> <td></td> <td></td> </tr> <tr> <td>138</td> <td>141</td> <td>SAND ROCK</td> <td></td> <td></td> <td></td> </tr> <tr> <td>141</td> <td>160</td> <td>FINE - MED SAND</td> <td></td> <td></td> <td></td> </tr> <tr> <td>160</td> <td>190</td> <td>FINE - MED SAND CLAY LAYERS</td> <td></td> <td></td> <td></td> </tr> <tr> <td>190</td> <td>210</td> <td>CLAY TAN IN COLOR ROCK LAYERS</td> <td></td> <td></td> <td></td> </tr> </tbody> </table>						FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS	0	20	TOPSOIL CLAY				20	40	CLAY				40	60	CLAY FINE SAND				60	100	FINE SAND				100	120	FINE - MED SAND				120	138	FINE SAND COARSE SAND SMALL GRAVEL				138	141	SAND ROCK				141	160	FINE - MED SAND				160	190	FINE - MED SAND CLAY LAYERS				190	210	CLAY TAN IN COLOR ROCK LAYERS			
FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS																																																																		
0	20	TOPSOIL CLAY																																																																					
20	40	CLAY																																																																					
40	60	CLAY FINE SAND																																																																					
60	100	FINE SAND																																																																					
100	120	FINE - MED SAND																																																																					
120	138	FINE SAND COARSE SAND SMALL GRAVEL																																																																					
138	141	SAND ROCK																																																																					
141	160	FINE - MED SAND																																																																					
160	190	FINE - MED SAND CLAY LAYERS																																																																					
190	210	CLAY TAN IN COLOR ROCK LAYERS																																																																					
7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 04/18/98 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 179 This Water Well Record was completed on (mo/day/yr) 05/11/98 under the business name of JOE'S WELL SERVICE, INC. by (signature) <i>Joel Cook</i>																																																																							

RECEIVED

JUN 18 1998

BUREAU OF WATER

(Continued)

WATER WELL RECORD Form WWC-5 KSA 82a-1212

1 LOCATION OF WATER WELL: COUNTY: FORD		Fraction SW 1/4 SE 1/4 SW 1/4	Section Number 36	Township Number T 27 S	Range Number R 25 W					
2 WATER WELL OWNER: RR#, St. Address, Box # : City, State, ZIP code :		GEUITZEN, TINA PHEASANT DRAW SUBDIVISION DODGE CITY, KS 67801-								
		Board of Agriculture, Division of Water Resources Application Number:								
<table border="1"> <thead> <tr> <th>FROM</th> <th>TO</th> <th>LITHOLOGIC LOG</th> </tr> </thead> <tbody> <tr> <td>210</td> <td>220</td> <td>BLUE SHALE</td> </tr> </tbody> </table>		FROM	TO	LITHOLOGIC LOG	210	220	BLUE SHALE			
FROM	TO	LITHOLOGIC LOG								
210	220	BLUE SHALE								