

1 LOCATION OF WATER WELL: Fraction Section Number Township Number Range Number
 COUNTY: FORD NW 1/4 NW 1/4 NW 1/4 10 T 27 S R 25 E

Distance and direction from nearest town or city street address of well if located within city?
 FROM DODGE CITY - SOUTH JCT. 283-56 WEST 2 MILES

2 WATER WELL OWNER: COLLINGWOOD GRAIN INC.
 R/R, St. Address, Box #: P.O. BOX 1358 Board of Agriculture, Division of Water Resources
 City, State, ZIP code: DODGE CITY, KS 67801- Application Number:

3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX:

1	2	3	4	5	6	7	8
1	2	3	4	5	6	7	8
1	2	3	4	5	6	7	8
1	2	3	4	5	6	7	8
1	2	3	4	5	6	7	8
1	2	3	4	5	6	7	8
1	2	3	4	5	6	7	8
1	2	3	4	5	6	7	8

4 DEPTH OF COMPLETED WELL 212 ELEVATION: 0
 Depth(s) Groundwater Encountered 1. 0 ft. 2. 0 ft. 3. 0 ft.

WELL'S STATIC WATER LEVEL 96 ft. below land surface measured on mo/day/yr 08/08/94
 Pump testdata: Well water was 0 ft. after 0 hours pumping 0 gpm
 Estimated Yield 85 gpm: Well water was 0 ft. after 0 hours pumping 0 gpm
 Bore Hole Diameter 12 in. to 212 ft., and in. to 0 ft.

WELL WATER TO BE USED AS: INDUSTRY

Was a chemical/bacteriological sample submitted to department? No;
 If yes, mo/day/yr sample was submitted Water well disinfected? Yes

5 TYPE OF BLANK CASING USED: PVC CASING JOINTS: GLUED
 Blank casing diameter 6 in. to 212 ft., Dia in. to 0 ft., Dia in. to 0 ft.
 Casing height above land surface 12 in., weight 200 lbs/ft. Wall thickness or gauge No. 21
 TYPE OF SCREEN OR PERFORATION MATERIAL: PVC
 SCREEN OR PERFORATION OPENINGS ARE: SAW CUT

SCREEN PERFORATED INTERVALS: From 132 ft. to 152 ft., From 0 ft. to 0 ft.
 From 172 ft. to 212 ft., From 0 ft. to 0 ft.
 GRAVEL PACK INTERVALS: From 30 ft. to 212 ft., From 0 ft. to 0 ft.
 From 0 ft. to 0 ft., From 0 ft. to 0 ft.

6 GROUT MATERIAL BENTONITE
 Grout Intervals: From 0 ft. to 30 ft., From 0 ft. to 0 ft., From 0 ft. to 0 ft.
 What is the nearest source of possible contamination: SEPTIC TANK
 Direction from well? SOUTH How many feet? 100

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	40	TOPSOIL FINE - MED SAND			
40	120	MED-COARSE SAND GRAVEL CLAY			
120	130	COARSE SAND			
130	150	FINE SAND CLAY			
150	160	CLAY FINE SAND			
160	170	BROWN CLAY			
170	212	BROWN CLAY SAND			
212	220	SAND ROCK BLUE SHALE			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 09/06/94 and this record is true to the best of my knowledge and belief. Kansas
 Water Well Contractor's License No. 179 This Water Well Record was completed on (mo/day/yr) 09/06/94
 under the business name of JOE'S WELL SERVICE, INC. by (signature) *Justin Crink*