

1 LOCATION OF WATER WELL: Fraction Section Number Township Number Range Number
 COUNTY: FORD NE 1/4 NE NW 1/4 1/4 28 T 27 S R 26 W

Distance and direction from nearest town or city street address of well if located within city?
 FROM HOWELL, KS. - 1 MILE SOUTH AND 3/4 MILE EAST

2 WATER WELL OWNER: STANLEY, JACK
 RR#, St. Address, Box #: ROUTE #2
 City, State, ZIP code: DODGE CITY, KS 67801- Board of Agriculture, Division of Water Resources
 Application Number:

3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX:

1	W	NW	NE
2	SW	SE	

4 DEPTH OF COMPLETED WELL 206 ELEVATION: 0
 Depth(s) Groundwater Encountered 1. 0 ft. 2. 0 ft. 3. 0 ft.
 WELL'S STATIC WATER LEVEL 26 ft. below land surface measured on mo/day/yr 11/04/93
 Pump testdata: Well water was 0 ft. after 0 hours pumping 0 gpm
 Estimated Yield 250 gpm: Well water was 0 ft. after 0 hours pumping 0 gpm
 Bore Hole Diameter 8 in. to 206 ft., and in. to 0 ft.
 WELL WATER TO BE USED AS: DOMESTIC
 Was a chemical/bacteriological sample submitted to department? No;
 If yes, mo/day/yr sample was submitted Water well disinfected? Yes

5 TYPE OF BLANK CASING USED: PVC CASING JOINTS: GLUED
 Blank casing diameter 5 in. to 206 ft., Dia in. to 0 ft., Dia in. to 0 ft.
 Casing height above land surface 12 in., weight 200 lbs/ft. Wall thickness or gauge No. 21
 TYPE OF SCREEN OR PERFORATION MATERIAL: PVC
 SCREEN OR PERFORATION OPENINGS ARE: SAW CUT

SCREEN PERFORATED INTERVALS: From 162 ft. to 202 ft., From 0 ft. to 0 ft.
 From 0 ft. to 0 ft., From 0 ft. to 0 ft.
 GRAVEL PACK INTERVALS: From 40 ft. to 206 ft., From 0 ft. to 0 ft.
 From 0 ft. to 0 ft., From 0 ft. to 0 ft.

6 GROUT MATERIAL BENTONITE
 Grout intervals: From 0 ft. to 40 ft., From 0 ft. to 0 ft., From 0 ft. to 0 ft.
 What is the nearest source of possible contamination: GRAIN BINS
 Direction from well? SOUTH How many feet? 50

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	11	TOPSOIL SANDY CLAY			
11	35	COARSE SAND GRAVEL			
35	42	MEDIUM SAND CLAY			
42	84	BROWN CLAY			
84	90	FINE SAND CLAY			
90	125	SANDY CLAY FINE SAND			
125	142	FINE SAND CLAY			
142	160	MEDIUM SAND FINE SAND GRAVEL			
160	202	GRAVEL			
202	210	CLAY			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 11/23/93 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 179 This Water Well Record was completed on (mo/day/yr) 12/21/93 under the business name of JOE'S WELL SERVICE, INC. by (signature) *Joe's Well Service*

(Continued)

1 LOCATION OF WATER WELL: Fraction Section Number Township Number Range Number
 COUNTY: FORD NE 1/4 NE NW 1/4 1/4 28 T 27 S R 26 W

2 WATER WELL OWNER: STANLEY, JACK
 RR#, St. Address, Box #: ROUTE #2
 City, State, ZIP code: DODGE CITY, KS 67801- Board of Agriculture, Division of Water Resources
 Application Number:

FROM	TO	LITHOLOGIC LOG
210	220	BLUE SHALE