

WATER WELL RECORD Form WWC-5 KSA 82a-1212

1 LOCATION OF WATER WELL:	Fraction	Section Number	Township Number	Range Number
COUNTY: GRAY	SW 1/4 NE 1/4	4	T 27 S	R 27 W

Distance and direction from nearest town or city street address of well if located within city?
FROM CINARON, KS. - 4 SOUTH, 3 3/4 EAST AND 1/4 SOUTH

2 WATER WELL OWNER: VERN GOETZ - well # 3 - line shaft turbine well
BB#, St. Address, Box #: BOX 1317 Board of Agriculture, Division of Water Resources
City, State, ZIP code : DODGE CITY, KS 67801 Application Number: 17356

3 LOCATE WELL'S LOCATION WITH
AN "X" IN SECTION BOX:

1	W	N	NE	X	
M					E
e	SW		SE		

4 DEPTH OF COMPLETED WELL 190 ELEVATION: 0
Depth(s) Groundwater Encountered 1. 0 ft. 2. 0 ft. 3. 0 ft.

WELL'S STATIC WATER LEVEL 124 ft. below land surface measured on mo/day/yr 07/17/95
Pump test data: Well water was 0 ft. after 0 hours pumping 0 gpm
Estimated Yield 250 gpm: Well water was 0 ft. after 0 hours pumping 0 gpm
Bore Hole Diameter 17 in. to 190 ft., and in. to 0 ft.

WELL WATER TO BE USED AS: IRRIGATION
Was a chemical/bacteriological sample submitted to department? No ;
If yes, mo/day/yr sample was submitted Water well disinfected? Yes

5 TYPE OF BLANK CASING USED: PVC CASING JOINTS: GLUED
Blank casing diameter 10 in. to 190 ft., Dia in. to 0 ft., Dia in. to 0 ft.
Casing height above land surface 12 in., weight 200 lbs/ft. Wall thickness or gauge No. 21
TYPE OF SCREEN OR PERFORATION MATERIAL: PVC
SCREEN OR PERFORATION OPENINGS ARE: SAW CUT

SCREEN PERFORATED INTERVALS: From 120 ft. to 180 ft., From 0 ft. to 0 ft.
From 0 ft. to 0 ft., From 0 ft. to 0 ft.
GRAVEL PACK INTERVALS: From 20 ft. to 190 ft., From 0 ft. to 0 ft.
From 0 ft. to 0 ft., From 0 ft. to 0 ft.

6 GROUT MATERIAL BENTONITE
Grout Intervals: From 0 ft. to 20 ft., From 0 ft. to 0 ft., From 0 ft. to 0 ft.
What is the nearest source of possible contamination: IRRIGATION WELL
Direction from well? SOUTH How many feet? 300

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	20	TOPSOIL CLAY			
20	40	CLAY FINE SAND			
40	60	CLAY LAYERS FINE SAND			
60	80	CLAY LAYERS FINE SAND			
80	100	FINE SAND			
100	120	FINE - MED SAND GRAVEL			
120	152	MED-COARSE SAND GRAVEL VERY LOOSE			
152	157	CLAY LAYERS			
157	182	CLAY LAYERS FINE - MED SAND GRAVEL			
182	190	CLAY ROCK LAYERS BLUE SHALE			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 09/01/95 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 179 This Water Well Record was completed on (mo/day/yr) 09/08/95 under the business name of JOE'S WELL SERVICE, INC. by (signature) *Judith Creek*