

WATER WELL RECORD Form WWC-5 KSA 82a-1212

1 LOCATION OF WATER WELL:	Fraction	Section Number	Township Number	Range Number
COUNTY: GRAY	SE 1/4 SE 1/4 SE 1/4	12	T 27 S	R 27 W

Distance and direction from nearest town or city street address of well if located within city?
 FROM HOWELL, KS - 5 SOUTH & 2 WEST

2 WATER WELL OWNER:	JOHNSON CEMETARY	Board of Agriculture, Division of Water Resources
RR#, St. Address, Box #:	X EUGENE BEGGS	Application Number:
City, State, ZIP code:	ENSIGN, KS 67841	

3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX:	4 DEPTH OF COMPLETED WELL 211 ELEVATION: 0
	Depth(s) Groundwater Encountered 1. 0 ft. 2. 0 ft. 3. 0 ft.
	WELL'S STATIC WATER LEVEL 153 ft. below land surface measured on mo/day/yr 07/13/93 Pump testdata: Well water was 0 ft. after 0 hours pumping 0 gpm
1 NW NE	Estimated Yield 30 gpm: Well water was 0 ft. after 0 hours pumping 0 gpm
N W E	Bore Hole Diameter 9 in. to 211 ft., and in. to 0 ft.
e SW SE	WELL WATER TO BE USED AS: DOMESTIC
	Was a chemical/bacteriological sample submitted to department? No; If yes, mo/day/yr sample was submitted Water well disinfected? Yes
X	

5 TYPE OF BLANK CASING USED: PVC	CASING JOINTS: GLUED
Blank casing diameter 5 in. to 211 ft., Dia in. to 0 ft., Dia in. to 0 ft.	
Casing height above land surface 12 in., weight 200 lbs/ft. Wall thickness or gauge No. 21	
TYPE OF SCREEN OR PERFORATION MATERIAL: PVC	
SCREEN OR PERFORATION OPENINGS ARE: SAW CUT	

SCREEN PERFORATED INTERVALS:	From 171 ft. to 211 ft., From 0 ft. to 0 ft.
	From 0 ft. to 0 ft., From 0 ft. to 0 ft.
GRAVEL PACK INTERVALS:	From 35 ft. to 211 ft., From 0 ft. to 0 ft.
	From 0 ft. to 0 ft., From 0 ft. to 0 ft.

6 GROUT MATERIAL BENTONITE	
Grout intervals: From 5 ft. to 35 ft., From 0 ft. to 0 ft., From 0 ft. to 0 ft.	
What is the nearest source of possible contamination: ABANDONED WELL	
Direction from well? SOUTHWEST	How many feet? 30

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	20	TOPSOIL CLAY FINE SAND			
20	56	FINE SAND CLAY FINE SAND			
56	100	CLAY FINE SAND IN LAYERS			
100	120	CLAY FINE - MED SAND IN LAYERS			
120	121	ROCK LAYERS			
121	140	FINE - MED SAND SMALL GRAVEL VERY LOOSE			
140	151	COARSE SAND LARGE GRAVEL			
151	160	CLAY FINE SAND IN LAYERS			
160	200	FINE - MED SAND			
200	219	FINE - MED SAND COARSE SAND			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 07/13/93 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 179 This Water Well Record was completed on (mo/day/yr) 11/16/95 under the business name of JOE'S WELL SERVICE, INC.	by (signature) <i>Judie Clark</i>
--	-----------------------------------

(Continued)

WATER WELL RECORD Form WWC-5 KSA 82a-1212

1 LOCATION OF WATER WELL:	Fraction	Section Number	Township Number	Range Number
COUNTY: GRAY	SE 1/4 SE 1/4 SE 1/4	12	T 27 S	R 27 W

2 WATER WELL OWNER:	JOHNSON CEMETARY	Board of Agriculture, Division of Water Resources
RR#, St. Address, Box #:	X EUGENE BEGGS	Application Number:
City, State, ZIP code:	ENSIGN, KS 67841	

FROM	TO	LITHOLOGIC LOG
219	230	ROCK GRAY LAYER(S)
230	240	ROCK CLAY LAYERS BLUE SHALE