

1 LOCATION OF WATER WELL: Fraction Section Number Township Number Range Number
 COUNTY: 035 GRAY SW 1/4 SW 1/4 SW 1/4 10 T 27 S R 27 W

Distance and direction from nearest town or city street address of well if located within city?
 APPROX. 3 1/2 MILES NORTH & 2 MILES WEST OF ENSIGN

2 WATER WELL OWNER: BRYAN, DAVID
 RR#, St. Address, Box #: 22004 U ROAD Board of Agriculture, Division of Water Resources
 City, State, ZIP code: CIMARRON, KS 67835- Application Number:

3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX: 4 DEPTH OF COMPLETED WELL 210 ELEVATION: 0
 Depth(s) Groundwater Encountered 1. 0 ft. 2. 0 ft. 3. 0 ft.
 WELL'S STATIC WATER LEVEL 150 ft. below land surface measured on mo/day/yr 06/11/97
 Pump test data: Well water was 0 ft. after 0 hours pumping 0 gpm
 Estimated Yield 18 gpm: Well water was 0 ft. after 0 hours pumping 0 gpm
 Bore Hole Diameter 10 in. to 210 ft., and in. to 0 ft.
 WELL WATER TO BE USED AS: 01 DOMESTIC
 Was a chemical/bacteriological sample submitted to department? No;
 If yes, mo/day/yr sample was submitted Water well disinfected? Yes

5 TYPE OF BLANK CASING USED: 02 PVC CASING JOINTS: GLUED
 Blank casing diameter 5 in. to 210 ft., Dia in. to 0 ft., Dia in. to 0 ft.
 Casing height above land surface 12 in., weight 3 lbs/ft. Wall thickness or gauge No. .265
 TYPE OF SCREEN OR PERFORATION MATERIAL: 07 PVC
 SCREEN OR PERFORATION OPENINGS ARE: 03 MILL SLOT

SCREEN PERFORATED INTERVALS: From 170 ft. to 210 ft., From 0 ft. to 0 ft.
 From 0 ft. to 0 ft., From 0 ft. to 0 ft.
 GRAVEL PACK INTERVALS: From 25 ft. to 210 ft., From 0 ft. to 0 ft.
 From 0 ft. to 0 ft., From 0 ft. to 0 ft.

6 GROUT MATERIAL 03 BENTONITE
 Grout Intervals: From 5 ft. to 25 ft., From 0 ft. to 0 ft., From 0 ft. to 0 ft.
 What is the nearest source of possible contamination: 14 ABAND. WELL
 Direction from well? SOUTHEAST How many feet? 130

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	2	02 SILT			
2	25	04 SANDY CLAY 31 CALICHE			
25	67	07 FINE SAND 08 MEDIUM SAND 01 CLAY			
67	80	04 SANDY CLAY			
80	95	04 SANDY CLAY			
95	100	07 FINE SAND 08 MEDIUM SAND			
100	134	05 SAND 13 FINE GRAVEL 01 CLAY			
134	140	05 SAND 11 GRAVEL 01 CLAY			
140	171	07 FINE SAND 08 MEDIUM SAND 09 COARSE SAND			
171	177	04 SANDY CLAY			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was
 completed on (mo/day/year) 06/13/97 and this record is true to the best of my knowledge and belief. Kansas
 Water Well Contractor's License No. 145 This Water Well Record was completed on (mo/day/yr) 06/25/97
 under the business name of HENKLE DRILLING & SUPPLY by (signature)

(Continued)

WATER WELL RECORD Form WWC-5 KSA 82a-1212

1 LOCATION OF WATER WELL: Fraction Section Number Township Number Range Number
COUNTY: 035 GRAY SW 1/4 SW 1/4 SW 1/4 10 T 27 S R 27 W

2 WATER WELL OWNER: BRYAN, DAVID
RR#, St. Address, Box #: 22004 U ROAD Board of Agriculture, Division of Water Resources

City, State, ZIP code : CIMARRON, KS 67835- Application Number:

FROM	TO	LITHOLOGIC LOG
177	185	05 SAND 13 FINE GRAVEL 14 MED GRAVEL
185	220	05 SAND 04 SANDY CLAY 13 FINE GRAVEL
220	225	20 LIMESTONE
225	240	19 SHALE 20 LIMESTONE

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 06/13/97 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 145 This Water Well Record was completed on (mo/day/yr) 06/25/97 under the business name of HENKLE DRILLING & SUPPLY by (signature) *Bruce J. Reichert*