


USE TYPEWRITER OR BALL,
POINT PEN-PRESS FIRMLY;
PRINT CLEARLY.

WATER WELL RECORD
KSA 82a-1201-1215

Kansas Department of Health and
Environment-Division of Environment
(Water well Contractors)
Topeka, Kansas 66620

1. Location of well:	County Gray	Fraction NE 1/4 SW 1/4 SW 1/4	Section number 12	Township number T 27 S	Range number R 27 E	
2. Distance and direction from nearest town or city: 3 1/2 mi N of Ensign, KS on secondary road.	3. Owner of well: Howard Beggs R.R. or street: City, state, zip code: Ensign, Kansas 67841					
4. Locate with "X" in section below: 	Sketch map:					
5. Type and color of material	From	To	6. Bore hole dia. 26 in. Completion date 5/18/77 Well depth 231 ft.			
See Attachments						7. <input type="checkbox"/> Cable tool <input type="checkbox"/> Rotary <input type="checkbox"/> Driven <input type="checkbox"/> Dug <input type="checkbox"/> Hollow rod <input type="checkbox"/> Jetted <input type="checkbox"/> Bored <input checked="" type="checkbox"/> Reverse rotary
						8. Use: <input type="checkbox"/> Domestic <input type="checkbox"/> Public supply <input type="checkbox"/> Industry <input checked="" type="checkbox"/> Irrigation <input type="checkbox"/> Air conditioning <input type="checkbox"/> Stock <input type="checkbox"/> Lawn <input type="checkbox"/> Oil field water <input type="checkbox"/> Other
						9. Casing: Material Steel Height: Above or below Threaded <input type="checkbox"/> Welded <input checked="" type="checkbox"/> Surface 12 in. RMP <input type="checkbox"/> PVC <input type="checkbox"/> Weight 31 lbs./ft. Dia. 16 in. to 231 ft. depth Wall Thickness: inches or Dia. <input type="checkbox"/> in. to <input type="checkbox"/> ft. depth gage No. 188
						10. Screen: Manufacturer's name Johnson Type Continuous Dia. 16" Slot/gauze .100 Length 40' Set between 140 ft. and 160 ft. 190'-200' ft. and 220'-230' ft. Gravel pack? <input checked="" type="checkbox"/> Yes Size range of material 2" down
						11. Static water level: mo./day/yr. 151 ft. below land surface Date 5/23/77
						12. Pumping level below land surfaces: 215 ft. after <input type="checkbox"/> hrs. pumping 810 g.p.m. <input type="checkbox"/> ft. after <input type="checkbox"/> hrs. pumping <input type="checkbox"/> g.p.m. Estimated maximum yield 810 g.p.m.
						13. Water sample submitted: mo./day/yr. Yes <input checked="" type="checkbox"/> No <input type="checkbox"/> Date
						14. Well head completion: <input type="checkbox"/> Pitless adapter 12 Inches above grade
						15. Well grouted? <input checked="" type="checkbox"/> Yes With: <input type="checkbox"/> Neat cement <input checked="" type="checkbox"/> Bentonite <input type="checkbox"/> Concrete Depth: From 0 ft. to 10 ft.
						16. Nearest source of possible contamination: None ft. <input type="checkbox"/> Direction <input type="checkbox"/> Type Observed Well disinfected upon completion? Yes <input checked="" type="checkbox"/> No
						17. Pump: <input checked="" type="checkbox"/> Not installed Manufacturer's name <input type="checkbox"/> Model number <input type="checkbox"/> HP <input type="checkbox"/> Volts <input type="checkbox"/> Length of drop pipe <input type="checkbox"/> ft. capacity <input type="checkbox"/> g.p.m. Type: <input type="checkbox"/> Submersible <input type="checkbox"/> Turbine <input type="checkbox"/> Jet <input type="checkbox"/> Reciprocating <input type="checkbox"/> Centrifugal <input type="checkbox"/> Other
(Use a second sheet if needed)						20. Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. Henkie Drilling&Sply 145 Business name License No. Address Box 639, Garden City, KS Signed <i>E.L. Bothwell</i> Date 5/24/77 Authorized representative
18. Elevation: <input checked="" type="checkbox"/> Flat	19. Remarks:					
Topography: <input type="checkbox"/> Hill <input type="checkbox"/> Slope <input type="checkbox"/> Upland <input type="checkbox"/> Valley						

DRILLERS TEST LOG

CUSTOMERS NAME Howard Beaggs DATE 3-30-77
STREET ADDRESS TEST # 12 E. LOG Yes
CITY & STATE Ensign, KS DRILLER Martinez
COUNTY Gray QUARTER SW SECTION 12 TOWNSHIP 27 RANGE 27
LOCATION 700' S OF Test #11

GARDEN CITY, KS
Phone 276-3278

GARDEN CITY, KS HENKLE DRILLING & SUPPLY CO., INC. SUBLINNE, KS
Phone 276-3278 IRRIGATION HEADQUARTERS Phone 675-4311
TEST HOLES * * * * * IRRIGATION & INDUSTRIAL WELLS * * * * * STOCK WELLS

HENKLE DRILLING & SUPPLY CO., INC.

IRRIGATION HEADQUARTERS

SUBLETTE, KS
Phone 675-4311

TEST HOLES * * * * * IRRIGATION & INDUSTRIAL WELLS * * * * STOCK WELLS