

## WATER WELL RECORD Form WWC-5 KSA 82a-1212

1 LOCATION OF WATER WELL:	Fraction COUNTY: 035 GRAY SE 1/4 NW 1/4 SW 1/4	Section Number 36	Township Number T 27 S	Range Number R 27 W
---------------------------	--	----------------------	---------------------------	------------------------

Distance and direction from nearest town or city street address of well if located within city?  
HWY 56 & LARNED STREET ENSIGN, KS

## 2 WATER WELL OWNER: CITY OF ENSIGN

RR#, St. Address, Box # : PO BOX 40  
City, State, ZIP code : ENSIGN, KS 67841-0040

Board of Agriculture, Division of Water Resources  
Application Number: 38335

3 LOCATE WELL'S LOCATION WITH  
AN "X" IN SECTION BOX:

4 DEPTH OF COMPLETED WELL 303 ELEVATION: 0  
Depth(s) Groundwater Encountered 1. 0 ft. 2. 0 ft. 3. 0 ft.

WELL'S STATIC WATER LEVEL 198 ft. below land surface measured on mo/day/yr 08/05/04  
Pump test data: Well water was 0 ft. after 0 hours pumping 0 gpm

1	NW	NE	
M			E
i			Bore Hole Diameter 22 in. to 303 ft., and in. to 0 ft.
W			
\	X	SW	SE
/			

Estimated Yield 0 gpm: Well water was 0 ft. after 0 hours pumping 0 gpm

WELL WATER TO BE USED AS: 05 PUB. WTR SUP

Was a chemical/bacteriological sample submitted to department? No ;  
If yes, mo/day/yr sample was submitted Water well disinfected? Yes

## 5 TYPE OF BLANK CASING USED: 02 PVC

CASING JOINTS: OTHER JNT- SURELOCK

Blank casing diameter 8 in. to 303 ft., Dia in. to 0 ft., Dia in. to 0 ft.  
Casing height above land surface 12 in., weight 7 lbs/ft. Wall thickness or gauge No. .410

TYPE OF SCREEN OR PERFORATION MATERIAL: 07 PVC

SCREEN OR PERFORATION OPENINGS ARE: 03 MILL SLOT

SCREEN PERFORATED INTERVALS: From 243 ft. to 283 ft., From 0 ft. to 0 ft.

From 0 ft. to 0 ft., From 0 ft. to 0 ft.

GRAVEL PACK INTERVALS: From 50 ft. to 303 ft., From 0 ft. to 0 ft.  
From 0 ft. to 0 ft., From 0 ft. to 0 ft.

## 6 GROUT MATERIAL 02 CEMENT GROUT

Grout Intervals: From 0 ft. to 50 ft., From 0 ft. to 0 ft., From 0 ft. to 0 ft.

What is the nearest source of possible contamination: 14 ABANDONED WELL

Direction from well? SW

How many feet? 40

LITHOLOGIC LOG			PLUGGING INTERVALS		
FROM	TO		FROM	TO	
0	2	02 SILT			
2	98	04 SANDY CLAY			
98	152	07 FINE SAND 08 MEDIUM SAND 01 CLAY			
152	215	05 SAND			
215	283	05 SAND 11 GRAVEL			
283	284	31 CALICHE			
284	290	19 SHALE			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 07/31/04 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 145 This Water Well Record was completed on (mo/day/yr) 11/04/04 under the business name of HENKLE DRILLING & SUPPLY by (signature) *Don J. Richman Jr.*