

WATER WELL RECORD Form WWC-5 KSA 82a-1212

1 LOCATION OF WATER WELL:	Fraction	Section Number	Township Number	Range Number
COUNTY: GRAY	SE 1/4 SE 1/4 NE 1/4	34	T 27 S	R 28 W

Distance and direction from nearest town or city street address of well if located within city?
FROM CIMARRON, KS. - 10 S. ON HIGHWAY 23 - 1 WEST & 1/2 S.

2 WATER WELL OWNER: SKINNER, DON
RR#, St. Address, Box #: 1803 BURR PARKWAY
City, State, ZIP code : DODGE CITY, KS 67801- Application Number: Board of Agriculture, Division of Water Resources

3 LOCATE WELL'S LOCATION WITH 4 DEPTH OF COMPLETED WELL 272 ELEVATION: 0
AN "X" IN SECTION BOX: Depth(s) Groundwater Encountered 1. 0 ft. 2. 0 ft. 3. 0 ft.

SW	SE		
W		X	E
SW	SE		

WELL'S STATIC WATER LEVEL 198 ft. below land surface measured on mo/day/yr 09/18/95
Pump test data: Well water was 0 ft. after 0 hours pumping 0 gpm
Estimated Yield 40 gpm: Well water was 0 ft. after 0 hours pumping 0 gpm
Bore Hole Diameter 9 in. to 272 ft., and in. to 0 ft.
WELL WATER TO BE USED AS: DOMESTIC
Was a chemical/bacteriological sample submitted to department? No ;
If yes, mo/day/yr sample was submitted Water well disinfected? Yes

5 TYPE OF BLANK CASING USED: PVC CASING JOINTS: GLUED
Blank casing diameter 5 in. to 272 ft., Dia in. to 0 ft., Dia in. to 0 ft.

Casing height above land surface 12 in., weight 200 lbs/ft. Wall thickness or gauge No. 21

TYPE OF SCREEN OR PERFORATION MATERIAL: PVC

SCREEN OR PERFORATION OPENINGS ARE: SAW CUT

SCREEN PERFORATED INTERVALS: From 227 ft. to 267 ft., From 0 ft. to 0 ft.

From 0 ft. to 0 ft., From 0 ft. to 0 ft.

GRAVEL PACK INTERVALS: From 25 ft. to 272 ft., From 0 ft. to 0 ft.

From 0 ft. to 0 ft., From 0 ft. to 0 ft.

6 GROUT MATERIAL BENTONITE

Grout Intervals: From 0 ft. to 25 ft., From 0 ft. to 0 ft., From 0 ft. to 0 ft.

What is the nearest source of possible contamination: ABANDONED WELL

Direction from well? WEST

How many feet? 8

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	20	TOPSOIL CLAY			
20	40	TAN IN COLOR CLAY FINE SAND			
40	100	FINE SAND			
100	140	FINE SAND CLAY LAYERS			
140	160	CLAY			
160	235	FINE SAND COARSE SAND SMALL GRAVEL			
235	265	CLAY MED-COARSE SAND IN LAYERS			
265	275	ROCK LAYERS BLUE SHALE			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was

completed on (mo/day/year) 09/19/95 and this record is true to the best of my knowledge and belief. Kansas

Water Well Contractor's License No. 179 This Water Well Record was completed on (mo/day/yr) 09/21/95

under the business name of JOE'S WELL SERVICE, INC.

by (signature) *David Cusk*