

WATER WELL RECORD Form WWC-5 KSA 82a-1212

1 LOCATION OF WATER WELL:		Fraction	Section Number	Township Number	Range Number
COUNTY: GRAY	NE 1/4 SW 1/4 SW 1/4	17	T 27 S	R 28 W	

Distance and direction from nearest town or city street address of well if located within city:
FROM CIMARRON 8 MILES SOUTH ON HIGHWAY 23 & 3 1/2 WEST

2 WATER WELL OWNER:		BURCH, KEN	Board of Agriculture, Division of Water Resources
BB#, St. Address, Box # : R.R. 1			Application Number:
City, State, ZIP code : INGALLS, KS 67853-			

3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX:		4 DEPTH OF COMPLETED WELL 257 ELEVATION: 0									
1 mile <table border="1" style="border-collapse: collapse; text-align: center;"> <tr><td colspan="2">NW</td><td colspan="2">NE</td></tr> <tr><td colspan="2">SW</td><td colspan="2">SE</td></tr> </table>		NW		NE		SW		SE		Depth(s) Groundwater Encountered 1. 0 ft. 2. 0 ft. 3. 0 ft.	
		NW		NE							
		SW		SE							
		WELL'S STATIC WATER LEVEL 152 ft. below land surface measured on mo/day/yr 10/06/95									
		Pump test data: Well water was 0 ft. after 0 hours pumping 0 gpm									
Estimated Yield 25 gpm: Well water was 0 ft. after 0 hours pumping 0 gpm											
Bore Hole Diameter 9 in. to 257 ft. and in. to 0 ft.											
WELL WATER TO BE USED AS: DOMESTIC											
Was a chemical/bacteriological sample submitted to department? No ;											
If yes, mo/day/yr sample was submitted		Water well disinfected? Yes									

5 TYPE OF BLANK CASING USED: PVC		CASING JOINTS: GLOUED	
Blank casing diameter 5 in. to 257 ft., Dia	in. to 0 ft., Dia	in. to 0 ft.	
Casing height above land surface 12 in., weight 200 lbs/ft.	Wall thickness or gauge No. 21		
TYPE OF SCREEN OR PERFORATION MATERIAL: PVC			
SCREEN OR PERFORATION OPENINGS ARE: SAW CUT			

SCREEN PERFORATED INTERVALS:	From 232 ft. to 252 ft.	From 0 ft. to 0 ft.		
	From 0 ft. to 0 ft.	From 0 ft. to 0 ft.		
GRAVEL PACK INTERVALS:	From 25 ft. to 257 ft.	From 0 ft. to 0 ft.		
	From 0 ft. to 0 ft.	From 0 ft. to 0 ft.		

6 GROUT MATERIAL BENTONITE	
Grout Intervals: From 0 ft. to 25 ft., From 0 ft. to 0 ft., From 0 ft. to 0 ft.	
What is the nearest source of possible contamination: NONE - NEW SITE	
Direction from well?	How many feet? 0

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	40	TOPSOIL CLAY FINE SAND			
40	60	FINE - MED SAND CLAY LAYERS			
60	80	CLAY FINE SAND CALACHIE			
80	100	CLAY MEDIUM SAND			
100	120	MED-COARSE SAND THIN ROCK LAYER			
120	160	MED-COARSE SAND CLAY			
160	200	CLAY CALACHIE FINE - MED SAND			
200	240	MED-COARSE SAND			
240	252	MED-COARSE SAND			
252	260	CLAY ROCK LAYERS BLUE SHALE			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 10/10/95 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 179 This Water Well Record was completed on (mo/day/yr) 11/13/95 under the business name of JOE'S WELL SERVICE, INC. by (signature) <i>Judith Crist</i>	
---	--