

WATER WELL RECORD Form WWC-5 KSA 82a-1212

LOCATION OF WATER WELL:	Fraction NW 1/4 NW 1/4 NW 1/4	Section Number 14	Township Number T 27 S	Range Number R 28 W
-------------------------	----------------------------------	----------------------	---------------------------	------------------------

Distance and direction from nearest town or city street address of well if located within city?
FROM CINARROW ON HIGHWAY 23 - 6 SOUTH, 1 WEST & 1 SOUTH

WATER WELL OWNER: TOOTHAKER, EUGENE

RR#, St. Address, Box #: CINARROW, KS 67835-

Board of Agriculture, Division of Water Resources
Application Number:

LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX:	4 DEPTH OF COMPLETED WELL 200 ELEVATION: 0 Depth(s) Groundwater Encountered 1. 0 ft. 2. 0 ft. 3. 0 ft.
X NW NE SW SE	WELL'S STATIC WATER LEVEL 106 ft. below land surface measured on mo/day/yr 11/06/92 Pump test data: Well water was 0 ft. after 0 hours pumping 0 gpm Estimated Yield 35 gpm: Well water was 0 ft. after 0 hours pumping 0 gpm Bore Hole Diameter 8 in. to 200 ft., and in. to 0 ft. WELL WATER TO BE USED AS: DOMESTIC Was a chemical/bacteriological sample submitted to department? No ; If yes, mo/day/yr sample was submitted Water well disinfected? Yes

TYPE OF BLANK CASING USED: PVC CASING JOINTS: GLUED
Blank casing diameter 5 in. to 200 ft., Dia in. to 0 ft., Dia in. to 0 ft.
Casing height above land surface 12 in., weight 200 lbs/ft. Wall thickness or gauge No. 21

TYPE OF SCREEN OR PERFORATION MATERIAL: PVC
SCREEN OR PERFORATION OPENINGS ARE: SAW CUT

SCREEN PERFORATED INTERVALS: From 145 ft. to 165 ft., From 0 ft. to 0 ft.
From 175 ft. to 195 ft., From 0 ft. to 0 ft.
GRAVEL PACK INTERVALS: From 35 ft. to 200 ft., From 0 ft. to 0 ft.
From 0 ft. to 0 ft., From 0 ft. to 0 ft.

GROUT MATERIAL BENTONITE
Grout Intervals: From 5 ft. to 35 ft., From 0 ft. to 0 ft., From 0 ft. to 0 ft.

What is the nearest source of possible contamination: ABANDONED WELL

Direction from well? NORTH

How many feet? 10

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	20	TOPSOIL CLAY FINE SAND			
20	40	FINE SAND			
40	60	FINE SAND CLAY IN LAYERS			
60	80	FINE - MED SAND			
80	100	MED-COARSE SAND SMALL GRAVEL			
100	120	CLAY FINE SAND IN LAYERS			
120	140	CLAY CALACHIE ROCK			
140	143	CLAY ROCK LAYERS			
143	160	FINE - MED SAND			
160	180	CLAY LAYERS FINE - MED SAND			

CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 11/07/92 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 179 This Water Well Record was completed on (mo/day/yr) 12/05/92 under the business name of JOE'S WELL SERVICE, INC. by (signature) *Lauf Creek*

(Continued)

WATER WELL RECORD Form WWC-5 KSA 82a-1212

LOCATION OF WATER WELL:	Fraction NW 1/4 NW 1/4 NW 1/4	Section Number 14	Township Number T 27 S	Range Number R 28 W
-------------------------	----------------------------------	----------------------	---------------------------	------------------------

WATER WELL OWNER: TOOTHAKER, EUGENE

RR#, St. Address, Box #: CINARROW, KS 67835-

Board of Agriculture, Division of Water Resources
Application Number:

FROM	TO	LITHOLOGIC LOG
180	200	CLAY LAYERS FINE - MED SAND
200	210	CLAY ROCK LAYERS BLUE SHALE