

WATER WELL RECORD Form #WC-5 KSA 82a-1212

1 LOCATION OF WATER WELL:	Fraction	Section Number	Township Number	Range Number
	NE 1/4 SW 1/4 SE 1/4	1/4	1 23	T 27 S R 28 W

Distance and direction from nearest town or city street address of well if located within city?
9 MILES SOUTH OF CIMARRON ON WEST SIDE

12 WATER WELL OWNER: GRAY COUNTY FEED YARD

RR#, St. Address, Box # :	R.R. 2 BOX 13	Board of Agriculture, Division of Water Resources
City, State, ZIP code :	CIMARRON, KS 67835	Application Number: 40393

13 LOCATE WELL'S LOCATION WITH
AN "X" IN SECTION BOX:

4 DEPTH OF COMPLETED WELL	500	ELEVATION:	0
Depth(s) Groundwater Encountered	1.	0 ft.	2. 0 ft. 3. 0 ft.

WELL'S STATIC WATER LEVEL 168 ft. below land surface measured on 5/13/94
Pump test data: Well water was 0 ft. after 0 hours pumping 0 gpm

Estimated Yield 0 gpm: Well water was 0 ft. after 0 hours pumping 0 gpm

Bore Hole Diameter 17.5 in. to 500 ft., and in. to 0 ft.

WELL WATER TO BE USED AS: 03 FEEDLOT

Was a chemical/bacteriological sample submitted to department? No ;
If yes, mo/day/yr sample was submitted Water well disinfected? Yes

15 TYPE OF BLANK CASING USED: 02 PVC Casing joints: GLUED

Blank casing diameter 8 in. to 500 ft., Dia in. to 0 ft., Dia in. to 0 ft.
Casing height above land surface 12 in., weight 6 lbs/ft. Wall thickness or gauge No. .332

TYPE OF SCREEN OR PERFORATION MATERIAL: 07 PVC

SCREEN OR PERFORATION OPENINGS ARE: 03 MILL SLOT

SCREEN PERFORATED INTERVALS: From 380 ft. to 480 ft., From 0 ft. to 0 ft.
From 0 ft. to 0 ft., From 0 ft. to 0 ft.

GRAVEL PACK INTERVALS: From 25 ft. to 90 ft., From 280 ft. to 500 ft.
From 100 ft. to 260 ft., From 0 ft. to 0 ft.

16 GROUT MATERIAL 03 BENTONITE

Grout intervals: From 5 ft. to 25 ft., From 90 ft. to 100 ft., From 260 ft. to 280 ft.

What is the nearest source of possible contamination: NONE OBSERVED

Direction from well? How many feet? 0

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	2	01 CLAY			
2	85	07 FINE SAND			
85	101	01 CLAY			
101	135	07 FINE SAND 08 MEDIUM SAND			
135	158	07 FINE SAND 08 MEDIUM SAND 13 FINE GRAVEL			
158	176	07 FINE SAND 08 MEDIUM SAND 01 CLAY			
176	182	01 CLAY			
182	192	01 CLAY			
192	207	07 FINE SAND			
207	270	21 SHALE & LMST			

17 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 145 This Water Well Record was completed on (mo/day/yr) 05/09/94 under the business name of HENKLE DRILLING & SUPPLY by (signature)

(Continued)

WATER WELL RECORD Form WWC-5 KSA 82a-1212

1 LOCATION OF WATER WELL: | Fraction | Section Number | Township Number | Range Number |
| COUNTY: 035 GRAY | SW 1/4 NE 1/4 SE 1/4 | 23 | T 27 S | R 28 W |

2 WATER WELL OWNER: GRAY COUNTY FEED YARD

RR#, St. Address, Box #: R.R. 2 BOX 13
City, State, ZIP code : CIMARRON, KS 67835- Board of Agriculture, Division of Water Resources
Application Number: 40393

FROM | TO | LITHOLOGIC LOG

270	340	21 SHALE & LMST
340	360	21 SHALE & LMST
360	380	19 SHALE
380	480	23 SANDSTONE
480	560	01 CLAY

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 145 This Water Well Record was completed on (mo/day/yr) 05/09/94 under the business name of HENKLE DRILLING & SUPPLY by (signature) 