

WATER WELL RECORD Form WWC-5 KSA 82a-1212

1 LOCATION OF WATER WELL: Fraction Section Number Township Number Range Number
 COUNTY: 035 GRAY SE 1/4 NW 1/4 SE 1/4 06 T 27 S R 28 W

Distance and direction from nearest town or city street address of well if located within city?
 FROM CIMARRON; APPX 5 MILES SOUTH & 3 1/2 MILRS WBST

2 WATER WELL OWNER: DARRIN ADDISON
 RR#, St. Address, Box # : PO BOX 529 Board of Agriculture, Division of Water Resources
 City, State, ZIP code : CIMARRON, KS 67835-0529 Application Number: 21,037

3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX:

NW	NE	SE	SW

4 DEPTH OF COMPLETED WELL 265 ELEVATION: 0
 Depth(s) Groundwater Encountered 1. 0 ft. 2. 0 ft. 3. 0 ft.

WELL'S STATIC WATER LEVEL 184 ft. below land surface measured on mo/day/yr 06/06/05
 Pump test data: Well water was 233 ft. after 4 hours pumping 1489 gpm

Estimated Yield 0 gpm: Well water was 0 ft. after 0 hours pumping 0 gpm

Bore Hole Diameter 24 in. to 265 ft., and in. to 0 ft.

WELL WATER TO BE USED AS: 02 IRRIGATION

Was a chemical/bacteriological sample submitted to department? No ;
 If yes, mo/day/yr sample was submitted Water well disinfected? Yes

5 TYPE OF BLANK CASING USED: 01 STEEL CASING JOINTS: WELDED
 Blank casing diameter 16 in. to 265 ft., Dia in. to 0 ft., Dia in. to 0 ft.
 Casing height above land surface 12 in., weight 42 lbs/ft. Wall thickness or gauge No. .250
 TYPE OF SCREEN OR PERFORATION MATERIAL: 01 STEEL
 SCREEN OR PERFORATION OPENINGS ARE: 01 CONT. SLOT

SCREEN PERFORATED INTERVALS: From 210 ft. to 260 ft., From 0 ft. to 0 ft.
 From 0 ft. to 0 ft., From 0 ft. to 0 ft.
 GRAVEL PACK INTERVALS: From 20 ft. to 265 ft., From 0 ft. to 0 ft.
 From 0 ft. to 0 ft., From 0 ft. to 0 ft.

6 GROUT MATERIAL 03 BENTONITE
 Grout Intervals: From 0 ft. to 20 ft., From 0 ft. to 0 ft., From 0 ft. to 0 ft.
 What is the nearest source of possible contamination: NONE OBSERVED
 Direction from well? How many feet? 0

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	1	02 SILT			
1	20	04 SANDY CLAY 31 CALICHE 05 SAND			
20	60	07 FINE SAND 08 MEDIUM SAND 01 CLAY			
60	77	04 SANDY CLAY 05 SAND			
77	103	05 SAND 13 FINE GRAVEL 01 CLAY			
103	112	05 SAND 11 GRAVEL			
112	125	04 SANDY CLAY			
125	133	05 SAND			
133	148	04 SANDY CLAY			
148	162	01 CLAY 05 SAND			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 06/02/05 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 145 This Water Well Record was completed on (mo/day/yr) 08/10/05 under the business name of HENKLE DRILLING & SUPPLY by (signature)

(Continued)

WATER WELL RECORD Form WWC-5 KSA 82a-1212

1 LOCATION OF WATER WELL: Fraction Section Number Township Number Range Number
COUNTY: 035 GRAY SE 1/4 NW 1/4 SE 1/4 06 T 27 S R 28 W

2 WATER WELL OWNER: DARRIN ADDISON
RR#, St. Address, Box # : PO BOX 529 Board of Agriculture, Division of Water Resources
City, State, ZIP code : CIMARRON, KS 67835-0529 Application Number: 21,037

FROM	TO	LITHOLOGIC LOG
162	169	05 SAND
169	188	01 CLAY
188	195	05 SAND 13 FINE GRAVEL
195	202	01 CLAY
202	211	04 SANDY CLAY 05 SAND
211	220	05 SAND
220	225	04 SANDY CLAY
225	254	05 SAND 11 GRAVEL 28 ROCK
254	260	05 SAND 11 GRAVEL 01 CLAY
260	279	04 SANDY CLAY 01 CLAY
279	283	19 SHALE

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 06/02/05 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 145 This Water Well Record was completed on (mo/day/yr) 08/10/05 under the business name of HENKLE DRILLING & SUPPLY by (signature) *Sam J. Henkle*