

WATER WELL RECORD Form WWC-5 KSA 82a-1212

1 LOCATION OF WATER WELL:		1 Fraction		1 Section Number		1 Township Number		1 Range Number	
1 COUNTY: 035 GRAY		1 NW 1/4 SW 1/4 SE 1/4 1/26		1		1 T 27 S		1 R 28 W	
1 Distance and direction from nearest town or city street address of well if located within city? 1 APPROX. 5 3/4 WEST, 1 1/4 NORTH, & 1/3 MILE WEST FROM ENSIGN									
12 WATER WELL OWNER:		GRAY COUNTY FEEDYARD							
1 RR#, St. Address, Box # :		ROUTE 2, BOX 15A Board of Agriculture, Division of Water Resources							
1 City, State, ZIP code :		CIMARRON, KS 67835- Application Number: 40,575							
13 LOCATE WELL'S LOCATION WITH 1 AN "X" IN SECTION BOX:		1 4 DEPTH OF COMPLETED WELL 495		1 ELEVATION: 0					
		1 Depth(s) Groundwater Encountered		1 1. 0 ft. 2. 0 ft. 3. 0 ft.					
		1 WELL'S STATIC WATER LEVEL 170 ft. below land surface measured on mo/day/yr 04/28/95							
		1 Pump testdata: Well water was 0 ft. after 4 hours pumping 200 gpm							
1 NW		1 NE		1 Estimated Yield 200 gpm: Well water was 0 ft. after 0 hours pumping 0 gpm					
M									
W		E		1 Bore Hole Diameter 17 1/2 in. to 495 ft., and in. to 0 ft.					
e				1 WELL WATER TO BE USED AS: 03 FEEDLOT					
SW		SE		1 Was a chemical/bacteriological sample submitted to department? No ; 1 If yes, mo/day/yr sample was submitted Water well disinfected? Yes					
15 TYPE OF BLANK CASING USED: 02 PVC		CASING JOINTS: GLUED							
1 Blank casing diameter 8 in. to 495 ft., Dia in. to 0 ft., Dia in. to 0 ft.									
1 Casing height above land surface 12 in., weight 7 lbs/ft. Wall thickness or gauge No. .410									
1 TYPE OF SCREEN OR PERFORATION MATERIAL: 07 PVC									
1 SCREEN OR PERFORATION OPENINGS ARE: 03 MILL SLOT									
1 SCREEN PERFORATED INTERVALS:		From 395 ft. to 475 ft., From 0 ft. to 0 ft.							
		From 0 ft. to 0 ft., From 0 ft. to 0 ft.							
1 GRAVEL PACK INTERVALS:		From 280 ft. to 495 ft., From 0 ft. to 0 ft.							
		From 25 ft. to 260 ft., From 0 ft. to 0 ft.							
16 GROUT MATERIAL 03 BENTONITE									
1 Grout Intervals: From 5 ft. to 25 ft., From 260 ft. to 280 ft., From 0 ft. to 0 ft.									
1 What is the nearest source of possible contamination: NONE OBSERVED									
1 Direction from well?		How many feet? 0							
1 FROM 0 TO 3 05 SAND		1 LITHOLOGIC LOG		1 FROM 0 TO 1		1 PLUGGING INTERVALS			
1 3 6 04 SANDY CLAY 07 FINE SAND									
1 6 18 01 CLAY									
1 18 25 07 FINE SAND 04 SANDY CLAY									
1 25 121 07 FINE SAND 09 COARSE SAND 01 CLAY									
1 121 130 05 SAND 20 LIMESTONE 01 CLAY									
1 130 146 04 SANDY CLAY 20 LIMESTONE 07 FINE SAND									
1 146 170 05 SAND 13 FINE GRAVEL 28 ROCK									
1 170 215 05 SAND 13 FINE GRAVEL 14 MED GRAVEL									
1 215 251 04 SANDY CLAY 07 FINE SAND									
17 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 04/28/95 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 145 This Water Well Record was completed on (mo/day/yr) 05/02/95 under the business name of HENKLE DRILLING & SUPPLY by (signature)									

(Continued)

WATER WELL RECORD Form WWC-5 KSA 82a-1212

11 LOCATION OF WATER WELL: Fraction
 Section Number Township Number Range Number
COUNTY: 035 GRAY NW 1/4 SW 1/4 SE 1/4 26 T 27 S R 28 W

12 WATER WELL OWNER: GRAY COUNTY FEEDYARD
RR#, St. Address, Box #: ROUTE 2, BOX 15A
City, State, ZIP code : CIMARRON, KS 67835-
Board of Agriculture, Division of Water Resources
Application Number: 40,575

FROM TO LITHOLOGIC LOG

251	257	31 CALICHE 20 LIMESTONE
257	390	19 SHALE 20 LIMESTONE 31 CALICHE
390	471	23 SANDSTONE 31 CALICHE
471	481	31 CALICHE 20 LIMESTONE 01 CLAY

17 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 04/28/95 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 145 This Water Well Record was completed on (mo/day/yr) 05/02/95 under the business name of HENKLE DRILLING & SUPPLY

by (signature)

Bruce J. Richmire