

1 LOCATION OF WATER WELL:	Fraction	Section Number	Township Number	Range Number
COUNTY: GRAY	NE 1/4 NE 1/4 NE 1/4	22	T 27 S	R 29 W

Distance and direction from nearest town or city street address of well if located within city?
FROM MCGALLS - 9 MILES SOUTH ON BLACKTOP ROAD

2 WATER WELL OWNER: SCHMIDT, DAN
RR#, St. Address, Box #: 2250 11 DRIVE
City, State, ZIP code : MONTEZUMA, KS 67867-

Board of Agriculture, Division of Water Resources
Application Number:

3 LOCATE WELL'S LOCATION WITH
AN "X" IN SECTION BOX:

4 DEPTH OF COMPLETED WELL 305 ELEVATION: 0			
Depth(s) Groundwater Encountered 1. 0 ft. 2. 0 ft. 3. 0 ft.			

WELL'S STATIC WATER LEVEL 124 ft. below land surface measured on mo/day/yr 04/24/95
Pump testdata: Well water was 0 ft. after 0 hours pumping 0 gpm

1 NW NE
M W E
SW SE

Estimated Yield 50 gpm: Well water was 0 ft. after 0 hours pumping 0 gpm

WELL WATER TO BE USED AS: DOMESTIC

Was a chemical/bacteriological sample submitted to department? No;
If yes, mo/day/yr sample was submitted Water well disinfected? Yes

5 TYPE OF BLANK CASING USED: PVC CASING JOINTS: GLUED
Blank casing diameter 5 in. to 305 ft., Dia in. to 0 ft.. Dia in. to 0 ft.
Casing height above land surface 12 in. weight 200 lbs/ft. Wall thickness or gauge No. 21
TYPE OF SCREEN OR PERFORATION MATERIAL: PVC
SCREEN OR PERFORATION OPENINGS ARE: SAW CUT

SCREEN PERFORATED INTERVALS: From 280 ft. to 300 ft., From 0 ft. to 0 ft.
From 0 ft. to 0 ft., From 0 ft. to 0 ft.
GRAVEL PACK INTERVALS: From 40 ft. to 305 ft., From 0 ft. to 0 ft.
From 0 ft. to 0 ft., From 0 ft. to 0 ft.

6 GROUT MATERIAL BENTONITE
Grout Intervals: From 5 ft. to 40 ft., From 0 ft. to 0 ft., From 0 ft. to 0 ft.
What is the nearest source of possible contamination: SEPTIC TANK
Direction from well? NORTHEAST
How many feet? 100

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	50	TOPSOIL FINE SAND			
50	65	CLAY			
65	80	FINE - MED SAND SMALL GRAVEL			
80	138	MED-COARSE SAND SMALL GRAVEL VERY LOOSE			
138	160	CLAY			
160	180	CLAY TAN IN COLOR FINE - MED SAND			
180	200	FINE - MED SAND CLAY TAN IN COLOR			
200	260	CLAY TAN IN COLOR			
260	295	FINE - MED SAND SMALL GRAVEL			
295	305	CLAY BLUE SHALE			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 05/05/95 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 179 This Water Well Record was completed on (mo/day/yr) 05/11/95 under the business name of JOE'S WELL SERVICE, INC. by (signature) *Judie Creek*