

## **WATER WELL RECORD**

## Form WWC-5

Division of Water Resources App. No.

22,605

**7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION:** This water well was  constructed,  reconstructed, or  plugged under my jurisdiction and was completed on (mo/day/year) 5-13-09..... and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 208..... This Water Well Record was completed on (mo/day/year) 5-18-09..... under the business name of MINTER-WILSON DRLG. CO., INC...... by (signature) Nora Keller.....

**INSTRUCTIONS:** Use typewriter or ball point pen. **PLEASE PRESS FIRMLY** and **PRINT** clearly. Please fill in blanks and check the correct answers. Send three copies (white, blue, pink) to Kansas Department of Health and Environment, Bureau of Water, Geology Section, 1000 SW Jackson St., Suite 420, Topeka, Kansas 66612-1367. Telephone 785-296-5522. Send one copy to WATER WELL OWNER and retain one for your records. Include **fee** of \$5.00 for each constructed well. Visit us at <http://www.kdheks.gov/waterwell/index.html>

*The  
Professionals*

# MINTER-WILSON DRILLING CO.

INCORPORATED

Irrigation  
and Domestic  
Water Systems  
Complete Installation  
and Repairing

Phone 276-8269 • P.O. Box A • GARDEN CITY, KANSAS 67846

NAME            RALPH MILLERSHASKI  
COUNTY        GRAY  
DATE            10-30-08

LOCATION:     SW 1/4 19-27-29 - SOUTH OF PIERCEVILLE TO POPCORN  
                  FACTORY - 8-1/4 MILES EAST  
                  - SOUTHWEST CORNER

STATIC WATER LEVEL - APPROX. 225 FT.

## TEST #2

0' TO 2' - TOP SOIL  
2' TO 10' - BROWN SANDY CLAY - LOOSE  
10' TO 55' - BROWN CLAY  
55' TO 62' - FINE TO MEDIUM SAND & GRAVEL  
62' TO 145' - FINE TO MEDIUM SAND & GRAVEL - SOME COARSE  
145' TO 171' - BROWN CLAY  
171' TO 230' - BROWN SANDY CLAY  
230' TO 258' - FINE TO MEDIUM SAND & GRAVEL-BROWN ROCK MIXED  
258' TO 279' - BROWN CLAY  
279' TO 287' - YELLOW CLAY  
287' TO 290' - SHALE