

1 LOCATION OF WATER WELL: Fraction Section Number Township Number Range Number
 COUNTY: 035 GRAY NW 1/4 SE 1/4 NE 1/4 24 T 27 S R 29 W

Distance and direction from nearest town or city street address of well if located within city?
 APPROX. 6 MILES NORTH & 1/2 MILE WEST OF MONTEZUMA

2 WATER WELL OWNER: BINDLEY, RUBY V.
 RR#, St. Address, Box #: PO BOX 214 Board of Agriculture, Division of Water Resources
 City, State, ZIP code: MONTEZUMA, KS 67867-0214 Application Number: 13,097

3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX: 4 DEPTH OF COMPLETED WELL 316 ELEVATION: 0
 Depth(s) Groundwater Encountered 1. 0 ft. 2. 0 ft. 3. 0 ft.
 WELL'S STATIC WATER LEVEL 126 ft. below land surface measured on mo/day/yr 02/11/98
 Pump test data: Well water was 126 ft. after 4 hours pumping 1735 gpm
 Estimated Yield 1735 gpm: Well water was 0 ft. after 0 hours pumping 0 gpm
 Bore Hole Diameter 24 in. to 316 ft., and in. to 0 ft.
 WELL WATER TO BE USED AS: 02 IRRIGATION
 Was a chemical/bacteriological sample submitted to department? No ;
 If yes, mo/day/yr sample was submitted Water well disinfected? Yes

5 TYPE OF BLANK CASING USED: 01 STEEL CASING JOINTS: WELDED
 Blank casing diameter 16 in. to 316 ft., Dia in. to 0 ft., Dia in. to 0 ft.
 Casing height above land surface 12 in., weight 39 lbs/ft. Wall thickness or gauge No. .225
 TYPE OF SCREEN OR PERFORATION MATERIAL: 01 STEEL
 SCREEN OR PERFORATION OPENINGS ARE: 01 CONT. SLOT

SCREEN PERFORATED INTERVALS: From 243 ft. to 313 ft., From 0 ft. to 0 ft.
 From 0 ft. to 0 ft., From 0 ft. to 0 ft.
 GRAVEL PACK INTERVALS: From 20 ft. to 316 ft., From 0 ft. to 0 ft.
 From 0 ft. to 0 ft., From 0 ft. to 0 ft.

6 GROUT MATERIAL 03 BENTONITE
 Grout Intervals: From 0 ft. to 20 ft., From 0 ft. to 0 ft., From 0 ft. to 0 ft.
 What is the nearest source of possible contamination: 14 ABAND. WELL
 Direction from well? NORTH How many feet? 90

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	10	02 SILT 01 CLAY			
10	24	07 FINE SAND			
24	32	04 SANDY CLAY			
32	49	01 CLAY 31 CALICHE			
49	65	07 FINE SAND 01 CLAY 31 CALICHE			
65	98	08 MEDIUM SAND 09 COARSE SAND 13 FINE GRAVEL			
98	114	05 SAND 11 GRAVEL 01 CLAY			
114	128	01 CLAY			
128	133	05 SAND 11 GRAVEL			
133	147	31 CALICHE			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 02/07/98 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 145 This Water Well Record was completed on (mo/day/yr) 02/16/98 under the business name of HENKLE DRILLING & SUPPLY by (signature)

(Continued)

WATER WELL RECORD Form WWC-5 KSA 82a-1212

1 LOCATION OF WATER WELL: Fraction Section Number Township Number Range Number
COUNTY: 035 GRAY 1/4 N/C 1/4 NE 1/4 24 T 27 S R 29 W

2 WATER WELL OWNER: BINDLEY, RUBY V.

RR#, St. Address, Box #: PO BOX 214

Board of Agriculture, Division of Water Resources

City, State, ZIP code: MONTEZUMA, KS 67867-0214

Application Number: 13,097

FROM	TO	LITHOLOGIC LOG
147	160	31 CALICHE 01 CLAY 05 SAND
160	164	08 MEDIUM SAND 01 CLAY
164	193	04 SANDY CLAY
193	201	08 MEDIUM SAND 09 COARSE SAND
201	213	04 SANDY CLAY
213	229	04 SANDY CLAY 05 SAND
229	246	04 SANDY CLAY 31 CALICHE
246	262	08 MEDIUM SAND 09 COARSE SAND 01 CLAY
262	279	07 FINE SAND 08 MEDIUM SAND 01 CLAY
279	295	08 MEDIUM SAND 09 COARSE SAND
295	313	09 COARSE SAND
313	328	19 SHALE

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 02/07/98 and this record is true to the best of my knowledge and belief. Kansas

Water Well Contractor's License No. 145

This Water Well Record was completed on (mo/day/yr) 02/16/98

under the business name of HENKLE DRILLING & SUPPLY

by (signature)

Bruce J. Richman