

## WATER WELL RECORD Form WWC-5 KSA 82a-1212

1 LOCATION OF WATER WELL:	Fraction COUNTY: GRAY	1/4 NW 1/4 NW 1/4	Section Number 17	Township Number T 27 S	Range Number R 29 W
---------------------------	--------------------------	-------------------	----------------------	---------------------------	------------------------

Distance and direction from nearest town or city street address of well if located within city?  
FROM CINARROW, KS. - 5 SOUTH, 3 WEST, 2 SOUTH & 1/2 WEST

2 WATER WELL OWNER:	BURCH, KEN RR#, St. Address, Box #:	R.R. #1	Board of Agriculture, Division of Water Resources Application Number:
City, State, ZIP code	INGALLS, KS 67853-		

3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX:	4 DEPTH OF COMPLETED WELL 260 ELEVATION: 0 Depth(s) Groundwater Encountered 1. 0 ft. 2. 0 ft. 3. 0 ft.
X NW NE SW SE	WELL'S STATIC WATER LEVEL 160 ft. below land surface measured on mo/day/yr 06/08/94 Pump testdata: Well water was 0 ft. after 0 hours pumping 0 gpm Estimated Yield 30 gpm: Well water was 0 ft. after 0 hours pumping 0 gpm Bore Hole Diameter 9 in. to 260 ft., and in. to 0 ft. WELL WATER TO BE USED AS: DOMESTIC Was a chemical/bacteriological sample submitted to department? No ; If yes, mo/day/yr sample was submitted Water well disinfected? Yes

5 TYPE OF BLANK CASING USED: PVC	CASING JOINTS: GLUED
Blank casing diameter 5 in. to 260 ft., Dia in. to 0 ft., Dia in. to 0 ft.	
Casing height above land surface 12 in., weight 200 lbs/ft. Wall thickness or gauge No. 21	
TYPE OF SCREEN OR PERFORATION MATERIAL: PVC	
SCREEN OR PERFORATION OPENINGS ARE: SAW CUT	

SCREEN PERFORATED INTERVALS:	From 235 ft. to 255 ft., From 0 ft. to 0 ft.
	From 0 ft. to 0 ft., From 0 ft. to 0 ft.
GRAVEL PACK INTERVALS:	From 30 ft. to 260 ft., From 0 ft. to 0 ft.
	From 0 ft. to 0 ft., From 0 ft. to 0 ft.

6 GROUT MATERIAL BENTONITE	
Grout Intervals: From 5 ft. to 30 ft., From 0 ft. to 0 ft., From 0 ft. to 0 ft.	
What is the nearest source of possible contamination: ABANDONED WELL	
Direction from well? WEST	How many feet? 8

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	80	TOPSOIL CLAY SANDY			
80	100	SAND GRAVEL			
100	115	SANDY CLAY			
115	150	CALACHIE ROCK CLAY			
150	200	FINE SAND			
200	215	SAND CLAY LAYERS			
215	250	SAND GRAVEL			
250	255	CLAY ROCK			
255	260	BLUE SHALE			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 06/08/94 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 179 This Water Well Record was completed on (mo/day/yr) 07/28/94 under the business name of JOE'S WELL SERVICE, INC.	by (signature) <i>Judie Clegg</i>
--	-----------------------------------