


1 LOCATION OF WATER WELL: Sedgwick		FRACTION NE 1/4 SE 1/4 SE 1/4		Section Number 27		Township Number T 27 S		Range Number R 3W E/W	
Distance and direction from nearest town or city street address of well if located within city? 1/4 N. of Hwy. 54, W. side of Andale Rd. 651 S. 247th W. Goddard, Ks.									
2 WATER WELL OWNER: SEDGWICK COUNTY EMS (Post #7, Station #5)		Board of Agriculture, Division of Water Resource							
RR#, ST. ADDRESS, BOX #: 651 S. 247th West		Application Number: 67052							
CITY, STATE, ZIP CODE: Goddard, Kansas									
3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX: 		4 DEPTH OF COMPLETED WELL 75 ft. ELEVATION: Depth(s) groundwater Encountered 1 ft. 2 ft. 3 ft. WELL'S STATIC WATER LEVEL 29 FT. BELOW LAND SURFACE MEASURED ON 02/05/1993 Pump test data: Well water was ft. after hours pumping gpm Est. Yield gpm : Well water was ft. after hours pumping gpm Bore Hole Diameter 14 in. to 75 ft., and in. to ft. WELL WATER TO BE USED AS: 1 Domestic 3 Feedlot 5 Public water supply 8 Air conditioning 11 Injection well 2 Irrigation 4 Industrial 6 Oil field water supply 9 Dewatering 12 Other (Specify below) 7 Lawn and garden only 10 Monitoring well Was a chemical/bacteriological sample submitted to Department? Yes No ☒ ; If yes, mo/day/yr sample was submitted Water Well Disinfected? Yes ☒ No							
5 TYPE OF CASING USED: 1 Steel 3 RMP (SR) 2 PVC 4 ABS Blank casing Diameter 5 in. to 55 ft., Dia in. to ft., Dia in. to ft. Casing height above land surface 12 in., weight 2.35 lbs. / ft. Wall thickness or gauge No. .214 TYPE OF SCREEN OR PERFORATION MATERIAL: 1 Steel 3 Stainless Steel 5 Fiberglass 7 PVC 10 Asbestos-cement 2 Brass 4 Galvanized steel 6 Concrete tile 8 RMP (SR) 11 other (specify) 12 None used (open hole) SCREEN OR PERFORATION OPENING ARE: 1 Continuous slot 3 Mill slot 5 Gauzed wrapped 8 Saw cut 11 None (open hole) 2 Louvered shutter 4 Key punched 6 Wire wrapped 9 Drilled holes 7 Torch cut 10 Other (specify) SCREEN-PERFORATION INTERVALS: from 55 ft. to 75 ft., From ft. to ft. GRAVEL PACK INTERVALS: from 24 ft. to 75 ft., From ft. to ft. from ft. to ft., From ft. to ft.		CASING JOINTS: Glued ☒ Clamped Welded Threaded SDR-26 3 Bentonite hole plugger Grout Intervals: From 4 ft. to 24 ft., From 24 ft. to 26 ft., From ft. to ft. What is the nearest source of possible contamination: 1 Septic tank 4 Lateral lines 7 Pit privy 11 Fuel storage 14 Abandon water well 2 Sewer lines 5 Cess pool 8 Sewage lagoon 12 Fertilizer storage 15 Oil well/Gas well 3 Watertight sewer lines 6 Seepage pit 9 Feedyard 13 Insecticide storage 16 Other (specify below) Direction from well? West How many feet? 25							
FROM TO LITHOLOGIC LOG FROM TO PLUGGING INTERVALS									
0	3	topsoil							
3	11	gray clay							
11	20	tan clay							
20	26	gray clay							
26	30	tan clay							
30	36	sandy, tan clay							
36	58	sandy, tan and gray clay							
58	72	medium to coarse sand and fine to coarse gravel with few clay lenses (tan)							
72	76	red shale							
7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was (1) constructed, (2) reconstructed, or (3) plugged under my jurisdiction and was completed on (mo/day/year) 02/05/1993 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 236 This Water Well Record was completed on (mo/day/yr) 04/08/93 Under the business name of Harp Well & Pump Service, Inc by (signature) <i>Jane Frederick</i>									