

WATER WELL RECORD Form WWD-5 KSA 82a-1212

1 LOCATION OF WATER WELL: Fraction : Section Number : Township Number : Range Number
 COUNTY: 035 GRAY : NW 1/4 NE 1/4 SW 1/4 : 32 : T 27 S : R 30 W

Distance and direction from nearest town or city street address of well if located within city?
 APPROX. 8.5 MILES NORTH OF COPELAND.

2 WATER WELL OWNER: DONALDA STAUTH
 RR#, St. Address, Box #: P.O. BOX 396 Board of Agriculture, Division of Water Resources

3 CITY, STATE, ZIP CODE : COPELAND, KS 67867 Application Number: 10690

4 LOCATE WELL'S LOCATION WITH : 4 DEPTH OF COMPLETED WELL 442 ELEVATION: 0
 AN "X" IN SECTION BOX: Depth(s) Groundwater Encountered 1. 183 ft. 2. 0 ft. 3. 0 ft.

WELL'S STATIC WATER LEVEL 183 ft. below land surface measured on mo/day/yr 11/29/91
 Pump testdata: Well water was 226 ft. after 4 hours pumping 1790 gpm

1 NW NE : Estimated Yield 12 gpm; Well water was 226 ft. after 4 hours pumping 1790 gpm

M : W E : Bore Hole Diameter 24 in. to 442 ft., and in. to 0 ft.

e : X : WELL WATER TO BE USED AS: 02 IRRIGATION

SW SE : Was a chemical/bacteriological sample submitted to department? No ;
 If yes, mo/day/yr sample was submitted Water well disinfected? No

5 TYPE OF BLANK CASING USED: 01 STEEL CASING JOINTS: WELDED

Blank casing diameter 16 in. to 442 ft., Dia in. to 0 ft., Dia in. to 0 ft.

Casing height above land surface 12 in., weight 42 lbs/ft. Wall thickness or gauge No. .250

TYPE OF SCREEN OR PERFORATION MATERIAL: 01 STEEL

SCREEN OR PERFORATION OPENINGS ARE: 01 CONT. SLOT

SCREEN PERFORATED INTERVALS: From 237 ft. to 397 ft., From 0 ft. to 0 ft.

From 417 ft. to 437 ft., From 0 ft. to 0 ft.

GRAVEL PACK INTERVALS: From 20 ft. to 442 ft., From 0 ft. to 0 ft.

From 0 ft. to 0 ft., From 0 ft. to 0 ft.

6 GROUT MATERIAL 03 BENTONITE

Grout Intervals: From 0 ft. to 20 ft., From 0 ft. to 0 ft., From 0 ft. to 0 ft.

What is the nearest source of possible contamination: 14 ABAND. WELL

Direction from well? WEST How many feet? 100

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	2	01 CLAY			
2	11	01 CLAY			
11	26	04 SANDY CLAY 05 SAND			
26	52	07 FINE SAND 08 MEDIUM SAND 01 CLAY			
52	64	04 SANDY CLAY 23 SANDSTONE			
64	84	07 FINE SAND 08 MEDIUM SAND 01 CLAY			
84	103	04 SANDY CLAY 05 SAND 20 LIMESTONE			
103	162	17 SAND & GRAVEL 01 CLAY			
162	164	01 CLAY			
164	190	05 SAND 14 MED GRAVEL 01 CLAY			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 11/26/91 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 145 This Water Well Record was completed on (mo/day/yr) 02/04/92 under the business name of HENKLE DRILLING & SUPPLY by (signature) *Douglas T. Henkle*

(Continued)

WATER WELL RECORD Form WWC-5 KSA 82a-1212

1 LOCATION OF WATER WELL: | Fraction | Section Number | Township Number | Range Number
| COUNTY: 035 GRAY | NW 1/4 NE 1/4 SW 1/4 | 32 | T 27 S | R 30 W

2 WATER WELL OWNER: DONALDA STAUTH
| RR#, St. Address, Box #: P.O. BOX 396

Board of Agriculture, Division of Water Resources

3 City, State, ZIP code : COPELAND, KS 67867-

Application Number: 10690

FROM	TO	LITHOLOGIC LOG
190	212	17 SAND & GRAVL 28 ROCK 01 CLAY
212	228	04 SANDY CLAY 05 SAND
228	249	05 SAND 01 CLAY
249	265	05 SAND 28 ROCK
265	273	07 FINE SAND 08 MEDIUM SAND 01 CLAY
273	299	07 FINE SAND 01 CLAY 20 LIMESTONE
299	351	07 FINE SAND 08 MEDIUM SAND 01 CLAY
351	368	07 FINE SAND 08 MEDIUM SAND 01 CLAY
368	397	05 SAND 11 GRAVEL 28 ROCK
397	414	19 SHALE 23 SANDSTONE 28 ROCK
414	427	23 SANDSTONE 19 SHALE
427	439	23 SANDSTONE
439	460	19 SHALE 28 ROCK 01 CLAY

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 11/26/91 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 145 This Water Well Record was completed on (mo/day/yr) 02/04/92 under the business name of HENKLE DRILLING & SUPPLY

by (signature)

Douglas B. Henkle