

1 LOCATION OF WATER WELL: Fraction Section Number Township Number Range Number
 1 COUNTY: 035 GRAY NW 1/4 NW 1/4 SE 1/4 32 T 27 S R 30 W

1 Distance and direction from nearest town or city street address of well if located within city?

1 APPROX. 8 MILES NORTH OF COPELAND

12 WATER WELL OWNER: GARY JANTZ

1 RR#, St. Address, Box #: RT. 2, BOX 21
 1 City, State, ZIP code : MONTEZUMA, KS 67867-

Board of Agriculture, Division of Water Resources
 Application Number: 451 14,936

13 LOCATE WELL'S LOCATION WITH

1 AN "X" IN SECTION BOX:

1 WELL'S STATIC WATER LEVEL 181 ft. below land surface measured on mo/day/yr 04/21/93
 1 Pump testdata: Well water was 255 ft. after 4 hours pumping 1550 gpm
 1 Estimated Yield 1550 gpm: Well water was 0 ft. after 0 hours pumping 0 gpm
 1 Bore Hole Diameter 24 in. to 403 ft., and in. to 0 ft.
 1 WELL WATER TO BE USED AS: 02 IRRIGATION
 1 Was a chemical/bacteriological sample submitted to department? No ;
 1 If yes, mo/day/yr sample was submitted Water well disinfected? No
 1

15 TYPE OF BLANK CASING USED: 01 STEEL

CASING JOINTS: WELDED

1 Blank casing diameter 16 in. to 403 ft., Dia in. to 0 ft., Dia in. to 0 ft.

1 Casing height above land surface 12 in., weight 42 lbs/ft. Wall thickness or gauge No. .250

1 TYPE OF SCREEN OR PERFORATION MATERIAL: 01 STEEL

1 SCREEN OR PERFORATION OPENINGS ARE: 01 CONT. SLOT

1 SCREEN PERFORATED INTERVALS: From 253 ft. to 313 ft., From 0 ft. to 0 ft.
 1 From 320 ft. to 400 ft., From 0 ft. to 0 ft.

1 GRAVEL PACK INTERVALS: From 20 ft. to 403 ft., From 0 ft. to 0 ft.
 1 From 0 ft. to 0 ft., From 0 ft. to 0 ft.

16 GROUT MATERIAL 03 BENTONITE

1 Grout Intervals: From 0 ft. to 20 ft., From 0 ft. to 0 ft., From 0 ft. to 0 ft.

1 What is the nearest source of possible contamination: 14 ABAND. WELL

1 Direction from well? EAST

How many feet? 250

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	34	04 SANDY CLAY			
34	90	07 FINE SAND 08 MEDIUM SAND 01 CLAY			
90	100	01 CLAY			
100	219	07 FINE SAND 09 COARSE SAND 15 CRS GRAVEL			
219	225	01 CLAY			
225	251	01 CLAY 07 FINE SAND			
251	267	07 FINE SAND 08 MEDIUM SAND			
267	280	04 SANDY CLAY 20 LIMESTONE 07 FINE SAND			
280	290	01 CLAY 20 LIMESTONE			
290	295	07 FINE SAND			

17 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was

1 completed on (mo/day/year) and this record is true to the best of my knowledge and belief. Kansas

1 Water Well Contractor's License No. 145 This Water Well Record was completed on (mo/day/yr) 04/23/93

1 under the business name of HENKLE DRILLING & SUPPLY by (signature)

(Continued)

WATER WELL RECORD Form WWC-5 KSA 82a-1212

11 LOCATION OF WATER WELL:	Fraction	Section Number	Township Number	Range Number
1 COUNTY: 035 GRAY	1 NW 1/4 NW 1/4 SE 1/4	1 32	1 T 27 S	1 R 30 W
12 WATER WELL OWNER:	GARY JANTZ			
1 RR#, St. Address, Box #:	RT. 2, BOX 21			
1 City, State, ZIP code:	MONTEZUMA, KS 67867-			

Board of Agriculture, Division of Water Resources
Application Number: 451 14,936

FROM TO LITHOLOGIC LOG

295	327	01 CLAY 20 LIMESTONE
327	345	07 FINE SAND 08 MEDIUM SAND
345	375	07 FINE SAND 08 MEDIUM SAND 04 SANDY CLAY
375	398	09 COARSE SAND 13 FINE GRAVEL 14 MED GRAVEL
398	412	31 CALICHE 23 SANDSTONE
412	420	19 SHALE

17 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 145 This Water Well Record was completed on (mo/day/yr) 04/23/93 under the business name of HENKLE DRILLING & SUPPLY

by (signature)

Benj. Reckmuth