

## WATER WELL RECORD Form WWD-5 KSA 82a-1212

1 LOCATION OF WATER WELL: Fraction : Section Number : Township Number : Range Number  
 COUNTY: 035 GRAY NW 1/4 NW 1/4 NE 1/4 34 T 27 S R 30 W

Distance and direction from nearest town or city street address of well if located within city?  
 APPROX. 7.5 MILES WEST AND 4 MILES NORTH OF MONTEZUMA.

2 WATER WELL OWNER: ERVIN NICHOLS  
 RR#, St. Address, Box #: RT. 3, BOX 79 Board of Agriculture, Division of Water Resources

City, State, ZIP code : SCOTT CITY, KS 67871 Application Number: 10241 AND 20284

3 LOCATE WELL'S LOCATION WITH 4 DEPTH OF COMPLETED WELL 411 ELEVATION: 0  
 AN "X" IN SECTION BOX: Depth(s) Groundwater Encountered 1. 168 ft. 2. 0 ft. 3. 0 ft.  
 X WELL'S STATIC WATER LEVEL 168 ft. below land surface measured on mo/day/yr 12/26/91  
 Pump testdata: Well water was 207 ft. after 4 hours pumping 1851 gpm  
 NW NE Estimated Yield 1400 gpm: Well water was 0 ft. after 0 hours pumping 0 gpm  
 W E Bore Hole Diameter 24 in. to 411 ft., and in. to 0 ft.  
 SW SE WELL WATER TO BE USED AS: 02 IRRIGATION  
 Was a chemical/bacteriological sample submitted to department? No ;  
 If yes, mo/day/yr sample was submitted Water well disinfected? No

5 TYPE OF BLANK CASING USED: 01 STEEL CASING JOINTS: WELDED  
 Blank casing diameter 16 in. to 411 ft., Dia in. to 0 ft., Dia in. to 0 ft.  
 Casing height above land surface 12 in., weight 37 lbs/ft. Wall thickness or gauge No. .219  
 TYPE OF SCREEN OR PERFORATION MATERIAL: 01 STEEL  
 SCREEN OR PERFORATION OPENINGS ARE: 01 CONT. SLOT

SCREEN PERFORATED INTERVALS: From 298 ft. to 408 ft., From 0 ft. to 0 ft.  
 From 0 ft. to 0 ft., From 0 ft. to 0 ft.  
 GRAVEL PACK INTERVALS: From 20 ft. to 411 ft., From 0 ft. to 0 ft.  
 From 0 ft. to 0 ft., From 0 ft. to 0 ft.

6 GROUT MATERIAL 03 BENTONITE  
 Grout Intervals: From 0 ft. to 20 ft., From 0 ft. to 0 ft., From 0 ft. to 0 ft.  
 What is the nearest source of possible contamination: 14 ABAND. WELL  
 Direction from well? NORTH How many feet? 264

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	1	01 CLAY			
1	20	04 SANDY CLAY 07 FINE SAND			
20	35	04 SANDY CLAY 20 LIMESTONE			
35	71	06 VERY FN SAND 07 FINE SAND 04 SANDY CLAY			
71	90	01 CLAY 20 LIMESTONE 07 FINE SAND			
90	95	01 CLAY 07 FINE SAND			
95	165	05 SAND 13 FINE GRAVEL 15 CRS GRAVEL			
165	205	23 SANDSTONE 05 SAND 01 CLAY			
205	217	07 FINE SAND 08 MEDIUM SAND			
217	227	23 SANDSTONE			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 12/20/91 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 145 This Water Well Record was completed on (mo/day/yr) 02/06/92 under the business name of HENKLE DRILLING & SUPPLY by (signature) *Douglas B. Henkle*

(Continued)

WATER WELL RECORD Form WWD-5 KSA 82a-1212

1 LOCATION OF WATER WELL:	Fraction	Section Number	Township Number	Range Number
COUNTY: 035 GRAY	NW 1/4 NW 1/4 NE 1/4	34	T 27 S	R 30 W

2 WATER WELL OWNER: ERVIN NICHOLS  
RR#, St. Address, Box #: RT. 3, BOX 79

Board of Agriculture, Division of Water Resources

3 City, State, ZIP code : SCOTT CITY, KS 67871-

Application Number: 10241 AND 20284

FROM	TO	LITHOLOGIC LOG
227	245	07 FINE SAND 08 MEDIUM SAND
245	280	20 LIMESTONE 01 CLAY 07 FINE SAND
280	290	01 CLAY
290	328	07 FINE SAND 04 SANDY CLAY
328	350	07 FINE SAND 01 CLAY
350	400	05 SAND 14 MED GRAVEL 28 ROCK
400	408	05 SAND 14 MED GRAVEL 28 ROCK
408	426	01 CLAY 28 ROCK
426	434	19 SHALE
434	460	19 SHALE
460	490	19 SHALE

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 12/20/91 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 145 This Water Well Record was completed on (mo/day/yr) 02/06/92 under the business name of HENKLE DRILLING & SUPPLY

by (signature)

*Douglas R. Henkle*