

WATER WELL RECORD Form WWC-5 KSA 82a-1212

1 LOCATION OF WATER WELL: Fraction Section Number Township Number Range Number
 COUNTY: 041 HASKELL NE 1/4 SE 1/4 NW 1/4 7 T 27 S R 31 W

Distance and direction from nearest town or city street address of well if located within city?
 APPROX. 7 3/4 MILES SOUTH AND 4 MILES WEST OF PIERCEVILLE

2 WATER WELL OWNER: EDWARD GREGG
 RR#, St. Address, Box #: 2500 BURNEY DRIVE Board of Agriculture, Division of Water Resources
 City, State, ZIP code: COLUMBIA, KS 29205- Application Number: 7,600

3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX: 4 DEPTH OF COMPLETED WELL 415 ELEVATION: 0
 Depth(s) Groundwater Encountered 1. 0 ft. 2. 0 ft. 3. 0 ft.

WELL'S STATIC WATER LEVEL 165 ft. below land surface measured on mo/day/yr 03/05/94
 Pump test data: Well water was 211 ft. after 4 hours pumping 1671 gpm
 Estimated Yield 2000 gpm: Well water was 0 ft. after 0 hours pumping 0 gpm
 Bore Hole Diameter 24 in. to 415 ft., and in. to 0 ft.
 WELL WATER TO BE USED AS: 02 IRRIGATION
 Was a chemical/bacteriological sample submitted to department? No ;
 If yes, mo/day/yr sample was submitted Water well disinfected? No

5 TYPE OF BLANK CASING USED: 01 STEEL CASING JOINTS: WELDED
 Blank casing diameter 16 in. to 415 ft., Dia in. to 0 ft., Dia in. to 0 ft.
 Casing height above land surface 12 in., weight 42 lbs/ft. Wall thickness or gauge No. .250
 TYPE OF SCREEN OR PERFORATION MATERIAL: 01 STEEL
 SCREEN OR PERFORATION OPENINGS ARE: 01 CONT. SLOT

SCREEN PERFORATED INTERVALS: From 241 ft. to 281 ft., From 332 ft. to 412 ft.
 From 290 ft. to 310 ft., From 0 ft. to 0 ft.
 GRAVEL PACK INTERVALS: From 20 ft. to 415 ft., From 0 ft. to 0 ft.
 From 0 ft. to 0 ft., From 0 ft. to 0 ft.

6 GROUT MATERIAL 03 BENTONITE
 Grout Intervals: From 0 ft. to 20 ft., From 0 ft. to 0 ft., From 0 ft. to 0 ft.
 What is the nearest source of possible contamination: 14 ABAND. WELL
 Direction from well? SOUTHWEST How many feet? 290

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	1	02 SILT			
1	11	04 SANDY CLAY			
11	21	07 FINE SAND 04 SANDY CLAY			
21	47	01 CLAY			
47	86	08 MEDIUM SAND 09 COARSE SAND 15 CRS GRAVEL			
86	97	01 CLAY			
97	107	07 FINE SAND 08 MEDIUM SAND 09 COARSE SAND			
107	122	01 CLAY 07 FINE SAND			
122	160	08 MEDIUM SAND 09 COARSE SAND 14 MED GRAVEL			
160	170	01 CLAY 20 LIMESTONE			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 03/03/94 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 145 This Water Well Record was completed on (mo/day/yr) 04/11/94 under the business name of HENKLE DRILLING & SUPPLY by (signature)

(Continued)

WATER WELL RECORD Form WWC-5 KSA 82a-1212

1 LOCATION OF WATER WELL:	Fraction	Section Number	Township Number	Range Number
COUNTY: 041 HASKELL	NE 1/4 SE 1/4 NW 1/4	7	T 27 S	R 31 W

2 WATER WELL OWNER:	EDWARD GREGG	Board of Agriculture, Division of Water Resources
RR#, St. Address, Box # :	2500 BURNEY DRIVE	Application Number: 7,600
City, State, ZIP code :	COLUMBIA, KS 29205-	

FROM	TO	LITHOLOGIC LOG
170	190	08 MEDIUM SAND 09 COARSE SAND 11 GRAVEL
190	202	01 CLAY
202	238	01 CLAY 20 LIMESTONE
238	253	08 MEDIUM SAND 09 COARSE SAND 11 GRAVEL
253	255	01 CLAY
255	273	08 MEDIUM SAND 09 COARSE SAND 11 GRAVEL
273	275	01 CLAY
275	281	08 MEDIUM SAND 09 COARSE SAND 11 GRAVEL
281	295	01 CLAY
295	311	08 MEDIUM SAND 09 COARSE SAND 11 GRAVEL
311	314	01 CLAY
314	321	08 MEDIUM SAND 09 COARSE SAND 11 GRAVEL
321	333	01 CLAY
333	340	08 MEDIUM SAND 09 COARSE SAND 07 FINE SAND
340	343	01 CLAY
343	375	04 SANDY CLAY 05 SAND
375	384	04 SANDY CLAY 06 VERY FM SAND
384	404	04 SANDY CLAY 07 FINE SAND
404	412	04 SANDY CLAY 11 GRAVEL
412	432	31 CALICHE
432	435	19 SHALE

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 03/03/94 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 145 This Water Well Record was completed on (mo/day/yr) 04/11/94 under the business name of HENKLE DRILLING & SUPPLY by (signature) *Bruce J. Reichmuth*