

USE TYPEWRITER OR BALL  
POINT PEN-PRESS FIRMLY,  
PRINT CLEARLY.

WATER WELL RECORD  
KSA 82a-1201-1215

Kansas Department of Health and  
Environment-Division of Environment  
(Water well Contractors)  
Topeka, Kansas 66620

1. Location of well:		County <b>Haskell</b>	Fraction <b>NW 1/4 NW 1/4 SW 1/4</b>	Section number <b>#28</b>	Township number <b>T #27 S</b>	Range number <b>R #31</b>
2. Distance and direction from nearest town or city: <b>13 miles south 5 miles west of Pierceville, Ks.</b> Street address of well location if in city:				3. Owner of well: <b>Manford Nichols</b> R.R. or street: City, state, zip code: <b>Copeland, Kansas 67837</b>		
4. Locate with "X" in section below: N W E S 1 Mile 1 Mile			Sketch map: <b>SHED</b> <b>HOUSE</b> <b>SEWER</b> <b>NEW WELL</b> <b>BARN</b>			6. Bore hole dia. <b>8</b> in. Completion date <b>8-8-75</b> Well depth <b>303</b> ft.
5. Type and color of material			From	To	7. <input checked="" type="checkbox"/> Cable tool <input checked="" type="checkbox"/> Rotary <input type="checkbox"/> Driven <input type="checkbox"/> Dug <input type="checkbox"/> Hollow rod <input type="checkbox"/> Jetted <input type="checkbox"/> Bored <input type="checkbox"/> Reverse rotary	
<b>Top soil &amp; clay</b>			<b>0</b>	<b>15</b>	8. Use: <input checked="" type="checkbox"/> Domestic <input type="checkbox"/> Public supply <input type="checkbox"/> Industry <input type="checkbox"/> Irrigation <input type="checkbox"/> Air conditioning <input checked="" type="checkbox"/> Stock <input type="checkbox"/> Lawn <input type="checkbox"/> Oil field water <input type="checkbox"/> Other	
<b>Clay</b>			<b>15</b>	<b>30</b>	9. Casing: Material <b>RMP</b> Height: Above or <del>below</del> Threaded <input type="checkbox"/> Welded <input type="checkbox"/> Surface <b>12</b> in. RMP <input checked="" type="checkbox"/> PVC <input type="checkbox"/> Weight _____ lbs./ft. Dia. <b>5</b> in. to <b>303</b> ft. depth; Wall Thickness _____ inches or Dia. _____ in. to _____ ft. depth; gage No. <b>250</b>	
<b>Clay &amp; fine sand</b>			<b>30</b>	<b>45</b>	10. Screen: Manufacturer's name <b>Sunflower</b> Type <b>RMP</b> Dia. <b>5"</b> Slot/gauze <b>1/8"</b> Length <b>20 ft.</b> Set between <b>275</b> ft. and <b>295</b> ft. _____ ft. and _____ ft. Gravel pack? <b>yes</b> Size range of material <b>1/4"</b>	
<b>Medium to coarse sand (dry)</b>			<b>45</b>	<b>90</b>	11. Static water level: _____ mo./day/yr. <b>120</b> ft. below land surface Date <b>8-8-75</b>	
<b>Coarse sand &amp; clay</b>			<b>90</b>	<b>105</b>	12. Pumping level below land surfaces: <b>120</b> ft. after <b>1 1/2</b> hrs. pumping <b>50</b> g.p.m. _____ ft. after _____ hrs. pumping _____ g.p.m. Estimated maximum yield <b>50</b> g.p.m.	
<b>Clay &amp; coarse sand</b>			<b>105</b>	<b>120</b>	13. Water sample submitted: _____ mo./day/yr. <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No Date _____	
<b>Coarse sand &amp; clay</b>			<b>120</b>	<b>135</b>	14. Well head completion: <input checked="" type="checkbox"/> Pitless adapter <b>12</b> Inches above grade	
<b>Clay &amp; fine sand</b>			<b>135</b>	<b>150</b>	15. Well grouted? <b>yes</b> With: <input type="checkbox"/> Neat cement <input checked="" type="checkbox"/> Bentonite <input type="checkbox"/> Concrete Depth: From <b>8</b> ft. to <b>18</b> ft.	
<b>Fine to medium sand</b>			<b>150</b>	<b>165</b>	16. Nearest source of possible contamination: ft. <b>100</b> Direction <b>SE</b> Type <b>sewer</b> Well disinfected upon completion? <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No	
<b>Fine to Medium sand &amp; clay</b>			<b>165</b>	<b>180</b>	17. Pump: <input checked="" type="checkbox"/> Not installed Manufacturer's name _____ Model number _____ HP _____ Volts _____ Length of drop pipe _____ ft. capacity _____ g.p.m. Type: <input type="checkbox"/> Submersible <input type="checkbox"/> Turbine <input type="checkbox"/> Jet <input type="checkbox"/> Reciprocating <input type="checkbox"/> Centrifugal <input type="checkbox"/> Other	
<b>Clay</b>			<b>180</b>	<b>195</b>	20. Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. <b>JOE'S WELL SERVICE</b> <b>179</b> Business name License No. Address <b>Box 174 Cimarron, Ks.</b> Signed <b>Joey Crick</b> Date <b>12-20</b> Authorized representative	
<b>Blue clay</b>			<b>195</b>	<b>230</b>	18. Elevation: 19. Remarks:	
<b>Fine to medium sand</b>			<b>230</b>	<b>240</b>	Topography: <input type="checkbox"/> Hill <input type="checkbox"/> Slope <input checked="" type="checkbox"/> Upland <input type="checkbox"/> Valley	
<b>Medium sand</b>			<b>240</b>	<b>285</b>	(Use a second sheet if needed)	
<b>Medium sand &amp; clay</b>			<b>285</b>	<b>315</b>		

Forward the white, blue and pink copies to the Department of Health and Environment

Form WWC-5