

WATER WELL RECORD Form WWC-5 KSA 82a-1212

1 LOCATION OF WATER WELL: | Fraction | Section Number | Township Number | Range Number
 COUNTY: 041 HASKELL | NE 1/4 NE 1/4 SE 1/4 | 32 | T 27 S | R 31 W

Distance and direction from nearest town or city street address of well if located within city?
 APPROX. 11 1/2 MILES NORTH AND 6 MILES EAST OF SUBLETTE.

2 WATER WELL OWNER: JOHN ECK
 RR#, St. Address, Box #: RT. 1, BOX 360 Board of Agriculture, Division of Water Resources
 City, State, ZIP code: COPELAND, KS 67837- Application Number: 5,451

3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX: | 4 DEPTH OF COMPLETED WELL 603 | ELEVATION:
 Depth(s) Groundwater Encountered 1. ft. 2. ft. 3. ft.
 WELL'S STATIC WATER LEVEL 226 ft. below land surface measured on mo/day/yr 02/25/91
 Pump test data: Well water was 314 ft. after 4 hours pumping 1400 gpm
 Estimated Yield 1400 gpm: Well water was ft. after hours pumping gpm
 Bore Hole Diameter 24 in. to 603 ft., and in. to ft.
 WELL WATER TO BE USED AS: 02 IRRIGATION
 Was a chemical/bacteriological sample submitted to department? No;
 If yes, mo/day/yr sample was submitted Water well disinfected? No

5 TYPE OF BLANK CASING USED: 01 STEEL CASING JOINTS: WELDED
 Blank casing diameter 16 in. to 603 ft., Dia in. to ft., Dia in. to ft.
 Casing height above land surface 12 in., weight 42 lbs/ft. Wall thickness or gauge No. .250
 TYPE OF SCREEN OR PERFORATION MATERIAL: 01 STEEL
 SCREEN OR PERFORATION OPENINGS ARE: 01 CONT. SLOT

SCREEN PERFORATED INTERVALS: From 344 ft. to 404 ft., From 520 ft. to 530 ft.
 From 426 ft. to 466 ft., From 535 ft. to 575 ft.
 GRAVEL PACK INTERVALS: From 20 ft. to 603 ft., From ft. to ft.
 From ft. to ft., From ft. to ft.

6 GROUT MATERIAL 03 BENTONITE
 Grout intervals: From ft. to 20 ft., From ft. to ft., From ft. to ft.
 What is the nearest source of possible contamination: NONE OBSERVED
 Direction from well? How many feet?

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
	2	01 CLAY			
2	107	04 SANDY CLAY 20 LIMESTONE 07 FINE SAND			
107	239	07 FINE SAND 08 MEDIUM SAND 13 FINE GRAVEL			
239	251	04 SANDY CLAY			
251	344	01 CLAY			
344	403	07 FINE SAND 08 MEDIUM SAND 01 CLAY			
403	425	04 SANDY CLAY			
425	450	07 FINE SAND 08 MEDIUM SAND			
450	466	07 FINE SAND 08 MEDIUM SAND 13 FINE GRAVEL			
466	496	04 SANDY CLAY 20 LIMESTONE 07 FINE SAND			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 02/22/91 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 145 This Water Well Record was completed on (mo/day/yr) 04/06/91 under the business name of HENKLE DRILLING & SUPPLY by (signature) *Bruce Kerchmitt*

(Continued)

WATER WELL RECORD Form WWC-5 KSA 82a-1212

1 LOCATION OF WATER WELL:	Fraction	Section Number	Township Number	Range Number
COUNTY: 041 HASKELL	NE 1/4 NE 1/4 SE 1/4	32	T 27 S	R 31 W

2 WATER WELL OWNER:	JOHN ECK	Board of Agriculture, Division of Water Resources
RR#, St. Address, Box # :	RT. 1, BOX 360	Application Number: 5,451
City, State, ZIP code :	COPELAND, KS 67837-	

FROM	TO	LITHOLOGIC LOG
496	500	06 VERY FN SAND 07 FINE SAND
500	520	04 SANDY CLAY 20 LIMESTONE 07 FINE SAND
520	530	07 FINE SAND 08 MEDIUM SAND
530	537	04 SANDY CLAY 20 LIMESTONE
537	573	08 MEDIUM SAND 14 MED GRAVEL 01 CLAY
573	580	04 SANDY CLAY 05 SAND
580	600	23 SANDSTONE 19 SHALE 20 LIMESTONE
600	622	19 SHALE

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 02/22/91 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 145 This Water Well Record was completed on (mo/day/yr) 04/06/81 under the business name of HENKLE DRILLING & SUPPLY by (signature) *Bruce J. Reckmuth*