

WATER WELL RECORD Form WWC-5 KSA 82a-1212

1 LOCATION OF WATER WELL: COUNTY: 041 HASKELL	Fraction LOT 4 NW 1/4 NW 1/4	Section Number 03	Township Number T 27 S	Range Number R 31 W
--------------------------------------------------	---------------------------------	----------------------	---------------------------	------------------------

Distance and direction from nearest town or city street address of well if located within city?
FROM PLYMELL; APPX 5 MILES SOUTH & 9 MILES EAST

2 WATER WELL OWNER: KLEYSTUBER CATTLE CO INC
RR#, St. Address, Box #: 13060 S ROAD 20
City, State, ZIP code: GARDEN CITY, KS 67846-8805
Board of Agriculture, Division of Water Resources
Application Number: 18877

3 LOCATE WELL'S LOCATION WITH
AN "X" IN SECTION BOX:

/ \				
1	X NW		NE	
M				
i	W			E
l				
e				
\ /		SW	SE	

4 DEPTH OF COMPLETED WELL 335 ELEVATION: 0
Depth(s) Groundwater Encountered 1. 0 ft. 2. 0 ft. 3. 0 ft.

WELL'S STATIC WATER LEVEL 0 ft. below land surface measured on mo/day/yr
Pump test data: Well water was 0 ft. after 0 hours pumping 0 gpm
Estimated Yield 0 gpm: Well water was 0 ft. after 0 hours pumping 0 gpm

Bore Hole Diameter 24 in. to 335 ft., and in. to 0 ft.

WELL WATER TO BE USED AS: 02 IRRIGATION

Was a chemical/bacteriological sample submitted to department? No ;
If yes, mo/day/yr sample was submitted Water well disinfected? Yes

5 TYPE OF BLANK CASING USED: 01 STEEL CASING JOINTS: WELDED
Blank casing diameter 16 in. to 335 ft., Dia in. to 0 ft., Dia in. to 0 ft.
Casing height above land surface 12 in., weight 37 lbs/ft. Wall thickness or gauge No. .219
TYPE OF SCREEN OR PERFORATION MATERIAL: 01 STEEL
SCREEN OR PERFORATION OPENINGS ARE: 01 CONT. SLOT

SCREEN PERFORATED INTERVALS:	From 196 ft. to 236 ft.,	From 303 ft. to 323 ft.
	From 236 ft. to 256 ft.,	From 0 ft. to 0 ft.
GRAVEL PACK INTERVALS:	From 20 ft. to 335 ft.,	From 0 ft. to 0 ft.
	From 0 ft. to 0 ft.,	From 0 ft. to 0 ft.

6 GROUT MATERIAL 03 BENTONITE
Grout Intervals: From 0 ft. to 20 ft., From 0 ft. to 0 ft., From 0 ft. to 0 ft.
What is the nearest source of possible contamination: 14 ABAND. WELL
Direction from well? SOUTHWEST How many feet? 386

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	1	02 SILT			
1	20	05 SAND			
20	63	05 SAND 13 FINE GRAVEL 14 MED GRAVEL			
63	83	05 SAND 11 GRAVEL			
83	187	05 SAND 11 GRAVEL 01 CLAY			
187	196	04 SANDY CLAY 05 SAND			
196	203	05 SAND 11 GRAVEL 01 CLAY			
203	214	05 SAND 11 GRAVEL 01 CLAY			
214	220	04 SANDY CLAY			
220	234	05 SAND 01 CLAY			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 04/16/04 and this record is true to the best of my knowledge and belief. Kansas
Water Well Contractor's License No. 145 This Water Well Record was completed on (mo/day/yr) 08/26/04
under the business name of HENKLE DRILLING & SUPPLY by (signature) -

RECEIVED
SEP 20 2004
BUREAU OF WATER

(Continued)

WATER WELL RECORD Form WWC-5 KSA 82a-1212

1 LOCATION OF WATER WELL:	Fraction	Section Number	Township Number	Range Number
COUNTY: 041 HASKELL	LOT 4 1/4 NW 1/4 NW 1/4	03	T 27 S	R 31 W

2 WATER WELL OWNER: KLEYSTUBER CATTLE CO INC
RR#, St. Address, Box # : 13060 S ROAD 20
City, State, ZIP code : GARDEN CITY, KS 67846-8805

Board of Agriculture, Division of Water Resources
Application Number: 18877

FROM	TO	LITHOLOGIC LOG
234	263	04 SANDY CLAY 01 CLAY 05 SAND
263	310	04 SANDY CLAY 01 CLAY
310	323	05 SAND 01 CLAY
323	347	01 CLAY
347	350	01 CLAY 23 SANDSTONE
350	363	01 CLAY
363	378	01 CLAY 31 CALICHE
378	384	19 SHALE

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 04/16/04 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 145 This Water Well Record was completed on (mo/day/yr) 08/26/04 under the business name of HENKLE DRILLING & SUPPLY by (signature) *Bruce J. Reichman*