

WATER WELL RECORD Form WWC-5 KSA 82a-1212

1 LOCATION OF WATER WELL: Fraction Section Number Township Number Range Number
 COUNTY: 041 HASKELL 1/4 NC 1/4 SW 1/4 8 T 27 S R 32 W

Distance and direction from nearest town or city street address of well if located within city?
 APPROX. 16 1/2 MILES SOUTH AND 1 MILE EAST OF GARDEN CITY

2 WATER WELL OWNER: CLELIA TOWNS
 RR#, St. Address, Box #: 909 E. FAIR Board of Agriculture, Division of Water Resources
 City, State, ZIP code: GARDEN CITY, KS 67846- Application Number: 18,554

3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX: 4 DEPTH OF COMPLETED WELL 468 ELEVATION: 0
 Depth(s) Groundwater Encountered 1. 0 ft. 2. 0 ft. 3. 0 ft.

WELL'S STATIC WATER LEVEL 167 ft. below land surface measured on mo/day/yr 04/05/93
 Pump test data: Well water was 308 ft. after 4 hours pumping 1489 gpm

Estimated Yield 1400 gpm: Well water was 0 ft. after 0 hours pumping 0 gpm

Bore Hole Diameter 24 in. to 468 ft., and in. to 0 ft.

WELL WATER TO BE USED AS: 02 IRRIGATION

Was a chemical/bacteriological sample submitted to department? No;
 If yes, mo/day/yr sample was submitted Water well disinfected? No

5 TYPE OF BLANK CASING USED: 01 STEEL CASING JOINTS: WELDED
 Blank casing diameter 16 in. to 468 ft., Dia in. to 0 ft., Dia in. to 0 ft.
 Casing height above land surface 12 in., weight 42 lbs/ft. Wall thickness or gauge No. .250
 TYPE OF SCREEN OR PERFORATION MATERIAL: 01 STEEL
 SCREEN OR PERFORATION OPENINGS ARE: 01 CONT. SLOT

SCREEN PERFORATED INTERVALS: From 248 ft. to 328 ft., From 445 ft. to 465 ft.
 From 328 ft. to 418 ft., From 0 ft. to 0 ft.
 GRAVEL PACK INTERVALS: From 20 ft. to 468 ft., From 0 ft. to 0 ft.
 From 0 ft. to 0 ft., From 0 ft. to 0 ft.

6 GROUT MATERIAL 03 BENTONITE
 Grout intervals: From 0 ft. to 20 ft., From 0 ft. to 0 ft., From 0 ft. to 0 ft.
 What is the nearest source of possible contamination: 14 ABAND. WELL
 Direction from well? WEST How many feet? 75

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	1	03 SILTY CLAY			
1	6	07 FINE SAND			
6	46	04 SANDY CLAY 07 FINE SAND			
46	98	07 FINE SAND 09 COARSE SAND 14 MED GRAVEL			
98	104	01 CLAY 20 LIMESTONE			
104	160	07 FINE SAND 09 COARSE SAND 14 MED GRAVEL			
160	162	04 SANDY CLAY			
162	185	07 FINE SAND 09 COARSE SAND 14 MED GRAVEL			
185	186	20 LIMESTONE			
186	202	04 SANDY CLAY 20 LIMESTONE 07 FINE SAND			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) and this record is true to the best of my knowledge and belief. Kansas
 Water Well Contractor's License No. 145 This Water Well Record was completed on (mo/day/yr) 04/08/93
 under the business name of HENKLE DRILLING & SUPPLY by (signature)

(Continued)

WATER WELL RECORD Form WWC-5 KSA 82a-1212

1 LOCATION OF WATER WELL: Fraction Section Number Township Number Range Number
COUNTY: 041 HASKELL 1/4 NC 1/4 SW 1/4 8 T 27 S R 32 W

2 WATER WELL OWNER: CLELIA TOWNS

RR#, St. Address, Box # : 909 E. FAIR

Board of Agriculture, Division of Water Resources

City, State, ZIP code : GARDEN CITY, KS 67846-

Application Number: 18,554

FROM	TO	LITHOLOGIC LOG
202	212	04 SANDY CLAY 07 FINE SAND 08 MEDIUM SAND
212	230	04 SANDY CLAY
230	286	01 CLAY 20 LIMESTONE 05 SAND
286	292	04 SANDY CLAY 20 LIMESTONE
292	302	04 SANDY CLAY 09 COARSE SAND 14 MED GRAVEL
302	307	04 SANDY CLAY 01 CLAY 20 LIMESTONE
307	352	07 FINE SAND 09 COARSE SAND 14 MED GRAVEL
352	354	04 SANDY CLAY
354	389	07 FINE SAND 09 COARSE SAND 14 MED GRAVEL
389	405	20 LIMESTONE 04 SANDY CLAY 07 FINE SAND
405	412	04 SANDY CLAY
412	418	07 FINE SAND 08 MEDIUM SAND 01 CLAY
418	456	04 SANDY CLAY 07 FINE SAND
456	465	29 ROCK & SAND 23 SANDSTONE
465	468	31 CALICHE
468	472	19 SHALE

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) and this record is true to the best of my knowledge and belief. Kansas

Water Well Contractor's License No. 145

This Water Well Record was completed on (mo/day/yr) 04/08/93

under the business name of HENKLE DRILLING & SUPPLY

by (signature)

Bruce Reichman