

WATER WELL RECORD Form WWC-5 KSA 82a-1212

1 LOCATION OF WATER WELL: Fraction Section Number Township Number Range Number
 COUNTY: 041 HASKELL SE 1/4 SE 1/4 NW 1/4 17 T 27 S R 32 W

Distance and direction from nearest town or city street address of well if located within city?
 APPROX. 14.75 MILES NORTH OF SUBLETTE.

2 WATER WELL OWNER: TEE, INC.
 RR#, St. Address, Box #: P.O. BOX 413 Board of Agriculture, Division of Water Resources
 City, State, ZIP code : TAOS, NM 87851- Application Number:

3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX:

1	2	3	4
5	6	7	8
9	10	11	12

WELL'S STATIC WATER LEVEL 185 ft. below land surface measured on mo/day/yr 10/07/91
 Pump test data: Well water was 0 ft. after 0 hours pumping 0 gpm
 Estimated Yield 0 gpm: Well water was 0 ft. after 0 hours pumping 0 gpm
 Bore Hole Diameter 9.875 in. to 382 ft., and in. to 0 ft.
 WELL WATER TO BE USED AS: 01 DOMESTIC
 Was a chemical/bacteriological sample submitted to department? No ;
 If yes, mo/day/yr sample was submitted Water well disinfected? Yes

5 TYPE OF BLANK CASING USED: 02 PVC CASING JOINTS: GLUED
 Blank casing diameter 5 in. to 355 ft., Dia in. to 0 ft., Dia in. to 0 ft.
 Casing height above land surface 12 in., weight 3 lbs/ft. Wall thickness or gauge No. .265
 TYPE OF SCREEN OR PERFORATION MATERIAL: 07 PVC
 SCREEN OR PERFORATION OPENINGS ARE: 03 MILL SLOT

SCREEN PERFORATED INTERVALS: From 295 ft. to 355 ft., From 0 ft. to 0 ft.
 From 0 ft. to 0 ft., From 0 ft. to 0 ft.
 GRAVEL PACK INTERVALS: From 25 ft. to 355 ft., From 0 ft. to 0 ft.
 From 0 ft. to 0 ft., From 0 ft. to 0 ft.

6 GROUT MATERIAL 03 BENTONITE
 Grout Intervals: From 5 ft. to 25 ft., From 0 ft. to 0 ft., From 0 ft. to 0 ft.
 What is the nearest source of possible contamination: 14 ABAND. WELL
 Direction from well? SOUTH How many feet? 75

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	2	01 CLAY			
2	24	01 CLAY			
24	53	04 SANDY CLAY 07 FINE SAND			
53	130	05 SAND 11 GRAVEL 01 CLAY			
130	143	05 SAND 11 GRAVEL 01 CLAY			
143	144	28 ROCK			
144	164	05 SAND 14 MED GRAVEL 01 CLAY			
164	169	04 SANDY CLAY			
169	189	05 SAND 35 CLAY & GRAVEL 20 LIMESTONE			
189	210	04 SANDY CLAY 05 SAND 20 LIMESTONE			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 10/09/91 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 145 This Water Well Record was completed on (mo/day/yr) 11/22/91 under the business name of HENKLE DRILLING & SUPPLY by (signature) *Douglas A. Henkle*

(Continued)

WATER WELL RECORD Form WWC-5 KSA 82a-1212

1 LOCATION OF WATER WELL: Fraction Section Number Township Number Range Number
COUNTY: 041 HASKELL SE 1/4 SE 1/4 NW 1/4 17 T 27 S R 32 W

2 WATER WELL OWNER: TEE, INC.
RR#, St. Address, Box #: P.O. BOX 413 Board of Agriculture, Division of Water Resources
City, State, ZIP code : TAOS, NM 87851- Application Number:

SCREEN PERFORATED INTERVALS: From 0 ft. to 0 ft., From 0 ft. to 0 ft.
From 0 ft. to 0 ft., From 0 ft. to 0 ft.

FROM	TO	LITHOLOGIC LOG
276	283	28 ROCK 01 CLAY
283	292	05 SAND 11 GRAVEL 28 ROCK
292	294	01 CLAY
294	317	05 SAND 14 MED GRAVEL 28 ROCK
317	354	05 SAND 13 FINE GRAVEL 01 CLAY
354	382	04 SANDY CLAY 05 SAND

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 10/09/91 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 145 This Water Well Record was completed on (mo/day/yr) 11/22/91 under the business name of HENKLE DRILLING & SUPPLY by (signature) *Douglas B. Henkle*