

DRILLERS TEST LOG

CUSTOMERS NAME Russell Smith DATE 1-7-76
 STREET ADDRESS _____ TEST # Housewell
 CITY & STATE Sublette, KS DRILLER Livingston
 COUNTY Haskell QUARTER SE SECTION 36 TOWNSHIP 27 RANGE 32

LOCATION SE corner of the SE 1/4

%	DRILLED FOOTAGE		Description of Strata	Static Water Level
	From	Pay To		Proposed Well Depth
	0	2	Top soil	
	2	100	Brown clay, caliche & few fine sand st.	
	100	180	Sand fine to med coarse small to large gravel	
65	180	40	240 Sand fine to med coarse, small gravel & few clay st	
	240	260	Brown clay, rock ledges & few sand st.	
	260	290	Blue clay	
	290	304	Sand blue, fine to med coarse	
	304	330	Blue clay & rock ledges	
	330	350	Brown clay & few sand st.	
70	350	18	368 Sand fine to med coarse, small to med gravel	
	368	370	Brown sandy clay	
65	370	30	400 Sand fine to med coarse, small gravel	
70	400	17	417 Sand fine to med coarse, small to med gravel	
	417	420	Brown clay	
				Henkle "A" Gravel Pack
				5" Plastic
				380 - 350 Perf.
				350 - 240 Plain
				240 - 230 Perf.
				230 - 0 Plain
				4 sacks of Revert
				2 gal. chlorine

ARDEN CITY, KANSAS HENKLE DRILLING & SUPPLY CO., INC. SUBLETTE, KANSAS
 HOME 276-3275 IRRIGATION HEADQUARTERS PHONE 675-4311

EST HOLES*****STOCK WELLS*****IRRIGATION AND INDUSTRIAL WELLS*****