

*The
Professionals*

MINTER-WILSON DRILLING CO.

INCORPORATED

Irrigation
and Domestic
Water Systems
Complete Installation
and Repairing

Phone 276-8269 • P.O. Box A • GARDEN CITY, KANSAS 67846

Bob Nightengale
Haskell County
1/15/04

Location: NW $\frac{1}{4}$ 15-27-32 - From Garden City - 17 miles south to Georgetown,
3 miles east, 1,350 ft. south & 20 ft. east to well
Offset well - 153 ft. south & 42 ft. east

Static Water Level - 224 ft.

Test #2

0' to 1' - Top soil
1' to 16' - Brown clay
16' to 37' - Brown sandy clay
37' to 89' - Fine to medium sand & gravel - 10% clay
89' to 105' - Brown clay
105' to 120' - Fine to medium sand & gravel
120' to 127' - Brown sandy clay
127' to 134' - Fine to medium sand & gravel - 10% clay
134' to 141' - Brown sandy clay
141' to 164' - Fine to medium sand & gravel
164' to 183' - Brown clay
183' to 220' - Blue clay
220' to 257' - Blue clay - small gravel streak
257' to 269' - Blue clay
269' to 282' - Fine to medium sand & gravel - clay streak
282' to 286' - Brown sandy clay
286' to 316' - Fine to medium sand & gravel
316' to 340' - Fine to medium sand & gravel - clay streak
340' to 356' - Brown sandy clay
356' to 358' - Fine to medium sand & gravel
358' to 369' - Brown sandy clay
369' to 402' - Brown sandy clay - small white rock mixed
402' to 410' - Brown clay
410' to 430' - Brown sandy clay
430' to 436' - Yellow clay
436' to 440' - Gray clay
440' to 460' - Yellow clay
460' to 470' - Shale