

WATER WELL RECORD Form WWC-5 KSA 82a-1212

1 LOCATION OF WATER WELL: | Fraction | Section Number | Township Number | Range Number
 COUNTY: 041 HASKELL | NW 1/4 SW 1/4 NW 1/4 | 24 | T 27 S | R 32 W

Distance and direction from nearest town or city street address of well if located within city?
 APPROX. 13 1/2 MILES NORTH & 3 MILES EAST OF SUBLETTE

2 WATER WELL OWNER: MILLER TRUST-HENRY MILLER
 RR#, St. Address, Box #: HCR 1, BOX 49 Board of Agriculture, Division of Water Resources
 City, State, ZIP code: SUBLETTE, KS 67877- Application Number: 830 & 1374

3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX: | 4 DEPTH OF COMPLETED WELL 416 ELEVATION: 0
 Depth(s) Groundwater Encountered 1. 0 ft. 2. 0 ft. 3. 0 ft.

WELL'S STATIC WATER LEVEL 203 ft. below land surface measured on mo/day/yr 11/25/94
 Pump test data: Well water was 268 ft. after 4 hours pumping 1563 gpm

Estimated Yield 1500 gpm: Well water was 0 ft. after 0 hours pumping 0 gpm

Bore Hole Diameter 24 in. to 416 ft., and in. to 0 ft.

WELL WATER TO BE USED AS: 02 IRRIGATION

Was a chemical/bacteriological sample submitted to department? No;
 If yes, mo/day/yr sample was submitted Water well disinfected? Yes

5 TYPE OF BLANK CASING USED: 01 STEEL CASING JOINTS: WELDED
 Blank casing diameter 16 in. to 416 ft., Dia in. to 0 ft., Dia in. to 0 ft.
 Casing height above land surface 12 in., weight 42 lbs/ft. Wall thickness or gauge No. .250
 TYPE OF SCREEN OR PERFORATION MATERIAL: 01 STEEL
 SCREEN OR PERFORATION OPENINGS ARE: 01 CONT. SLOT

SCREEN PERFORATED INTERVALS: From 293 ft. to 413 ft., From 0 ft. to 0 ft.
 From 0 ft. to 0 ft., From 0 ft. to 0 ft.
 GRAVEL PACK INTERVALS: From 20 ft. to 416 ft., From 0 ft. to 0 ft.
 From 0 ft. to 0 ft., From 0 ft. to 0 ft.

6 GROUT MATERIAL 03 BENTONITE
 Grout intervals: From 0 ft. to 20 ft., From 0 ft. to 0 ft., From 0 ft. to 0 ft.
 What is the nearest source of possible contamination: 14 ABAND. WELL
 Direction from well? EAST How many feet? 230

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	2	02 SILT			
2	9	02 SILT 05 SAND			
9	32	04 SANDY CLAY 01 CLAY			
32	45	04 SANDY CLAY			
45	57	04 SANDY CLAY 05 SAND			
57	72	07 FINE SAND 09 COARSE SAND 11 GRAVEL			
72	76	01 CLAY			
76	82	09 COARSE SAND 11 GRAVEL			
82	140	07 FINE SAND 09 COARSE SAND 11 GRAVEL			
140	172	07 FINE SAND 08 MEDIUM SAND 09 COARSE SAND			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 11/22/94 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 145 This Water Well Record was completed on (mo/day/yr) 11/29/94 under the business name of HENKLE DRILLING & SUPPLY by (signature)

(Continued)

WATER WELL RECORD Form WWC-5 KSA 82a-1212

1 LOCATION OF WATER WELL: : Fraction : Section Number : Township Number : Range Number
: COUNTY: 041 HASKELL : NW 1/4 SW 1/4 NW 1/4 : 24 : T 27 S : R 32 W

2 WATER WELL OWNER: MILLER TRUST-HENRY MILLER
: RR#, St. Address, Box #: HCR 1, BOX 49 Board of Agriculture, Division of Water Resources
: City, State, ZIP code : SUBLETTE, KS 67877- Application Number: 830 & 1374

FROM	TO	LITHOLOGIC LOG
172	200	07 FINE SAND 08 MEDIUM SAND 01 CLAY
200	227	07 FINE SAND 08 MEDIUM SAND 09 COARSE SAND
227	247	01 CLAY
247	285	01 CLAY 07 FINE SAND
285	356	07 FINE SAND 08 MEDIUM SAND 09 COARSE SAND
356	413	07 FINE SAND 08 MEDIUM SAND 04 SANDY CLAY
413	432	04 SANDY CLAY 19 SHALE
432	462	01 CLAY 19 SHALE
462	480	31 CALICHE 01 CLAY

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 11/22/94 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 145 This Water Well Record was completed on (mo/day/yr) 11/29/94 under the business name of HENKLE DRILLING & SUPPLY

by (signature) *Bruce Reichmuth*