

1 LOCATION OF WATER WELL: Fraction Section Number Township Number Range Number
 COUNTY: 041 HASKELL NE 1/4 NW 1/4 SE 1/4 24 T 27 S R 33 W

Distance and direction from nearest town or city street address of well if located within city?
 FROM GARDEN CITY, 8M S; 1/2M W, 1/2M N & 1/8M E.

2 WATER WELL OWNER: GENE DAVIS
 RR#, St. Address, Box #: HRC. 1 P.O BOX 36 Board of Agriculture, Division of Water Resources
 City, State, ZIP code: SUBLETTE, KS 67870-036 Application Number: 12835

3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX: 4 DEPTH OF COMPLETED WELL 586 ELEVATION:
 Depth(s) Groundwater Encountered 1. 0 ft. 2. 0 ft. 3. 0 ft.

WELL'S STATIC WATER LEVEL 263 ft. below land surface measured on mo/day/yr 07/15/96
 Pump test data: Well water was 313 ft. after 2 hours pumping 1100 gpm
 Estimated Yield 1100 gpm: Well water was 0 ft. after 0 hours pumping 0 gpm
 Bore Hole Diameter 24 in. to 586 ft., and in. to 0 ft.
 WELL WATER TO BE USED AS: 02 IRRIGATION
 Was a chemical/bacteriological sample submitted to department? No;
 If yes, mo/day/yr sample was submitted Water well disinfected? Yes

5 TYPE OF BLANK CASING USED: 01 STEEL CASING JOINTS: WELDED
 Blank casing diameter 16 in. to 586 ft., Dia in. to 0 ft., Dia in. to 0 ft.
 Casing height above land surface 12 in., weight 42 lbs/ft. Wall thickness or gauge No. .025
 TYPE OF SCREEN OR PERFORATION MATERIAL: 01 STEEL
 SCREEN OR PERFORATION OPENINGS ARE: 01 CONT. SLOT

SCREEN PERFORATED INTERVALS: From 306 ft. to 586 ft., From 0 ft. to 0 ft.
 From 0 ft. to 0 ft., From 0 ft. to 0 ft.
 GRAVEL PACK INTERVALS: From 20 ft. to 586 ft., From 0 ft. to 0 ft.
 From 0 ft. to 0 ft., From 0 ft. to 0 ft.

6 GROUT MATERIAL 03 BENTONITE
 Grout Intervals: From 0 ft. to 20 ft., From 0 ft. to 0 ft., From 0 ft. to 0 ft.
 What is the nearest source of possible contamination: NONE OBSERVED
 Direction from well? How many feet? 0

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	46	BRWN SANDY CLAY CALICHE			
46	165	FN-ME-CRS SAND GRAVEL			
165	202	BRWN SANDY CLAY LIMESTONE SAND STREAKS			
202	267	FN-ME-CRS SAND GRAVEL			
267	272	BRWN SANDY CLAY			
272	298	FN-ME-CRS SAND GRAVEL BRWN CLAY STRKS			
298	310	CLAY			
310	440	FN-ME-CRS SAND GRAVEL			
440	451	FINE SAND BRWN SANDY CLAY			
451	500	FN-ME-CRS SAND GRAVEL			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 07/12/96 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 145 This Water Well Record was completed on (mo/day/yr) 07/17/96 under the business name of HENKLE DRILLING & SUPPLY by (signature) *Bruce J. Reichmuth*

(Continued)

WATER WELL RECORD Form WWC-5 KSA 82a-1212

1 LOCATION OF WATER WELL: : Fraction : Section Number : Township Number : Range Number
COUNTY: 041 HASKELL : NE 1/4 NW 1/4 SE 1/4 : 24 : T 27 S : R 33 W

2 WATER WELL OWNER: GENE DAVIS
RR#, St. Address, Box #: HRC. 1 P.O BOX 36 Board of Agriculture, Division of Water Resources
City, State, ZIP code : SUBLETTE, KS 67870-036 Application Number: 12835

FROM	TO	LITHOLOGIC LOG
500	586	23 SANDSTONE