



DRILLERS TEST LOG

CUSTOMERS NAME Master Land Co DATE 3-19-81  
 STREET ADDRESS Box 1054 TEST # 1 E. LOG Yes  
 CITY & STATE Garden City, KS 67846 DRILLER Mai  
 COUNTY Haskell QUARTER SW SECTION 3 TOWNSHIP 27 RANGE 33  
 LOCATION 30' N of Pivot Circle #3

Possible Well Location

%	FOOTAGE		DESCRIPTION OF STRATA	Static Water Level _____
	From	Pay To		Proposed Well Depth _____
	0	2	SANDY TOP SOIL	
	2	9	FINE SAND	
	9	47	BROWN SANDY CLAY & FINE SAND	
	47	60	SAND-FINE TO MED COURSE & SANDY CLAY STKS.	
	60	92	SAND-FINE TO MED COURSE SMALL TO LARGE GRAVEL	
	92	106	SAND-FINE TO MED COURSE SMALL TO LARGE GRAVEL & COBBLESTONE DRILLS ROUGH, USES WATER	
	106	114	SAND-FINE TO MED COURSE SMALL GRAVEL	
	114	119	BROWN CLAY	
	119	148	SAND-FINE TO MED COURSE SMALL TO MED GRAVEL	
	148	155	BROWN CLAY	
65	155	31 186	SAND-FINE TO MED COURSE SMALL TO MED GRAVEL FEW CLAY STKS	
	186	218	BROWN SANDY CLAY & BROWN & GRAY CLAY STKS, FEW SAND STKS	
20	218	7 225	SAND-FINE TO MED COURSE SMALL GRAVEL GRAY CLAY STKS	
	225	235	BLUE SAND-BLUE CLAY STKS	
	235	270	BLUE CLAY, MURKY IN PLACES, FEW CEMENTED LARGE	
30	270	18 288	BLUE SAND-FINE TO MED COURSE BLUE CLAY STKS	
80	288	16 304	SAND-FINE TO MED COURSE SMALL TO LARGE, GRAVEL ROUGH IN PLACES	
70	304	16 320	SAND-FINE TO MED COURSE SMALL TO MED GRAVEL	
60	320	18 338	SAND-FINE TO MED COURSE SMALL & FEW MED GRAVEL FEW SMALL CLAY STKS	
45	338	8 346	SAND-FINE TO MED COURSE & SANDY CLAY STK	
	346	356	BROWN SANDY CLAY, SAND STKS & FEW STICKY CLAY STKS	
55	356	10 366	SAND-FINE TO MED COURSE FEW LIMEROCK & GYP ROCK	
	366	376	BROWN SANDY CLAY SAND STKS	
35	376	14 390	SAND-FINE & SMALL	
	390	395	BROWN & BROWN SANDY CLAY	
20	395	9 404	SANDY CLAY & FINE SAND	
25	404	6 410	LIMEROCK, FINE SAND & SANDY CLAY	
	410	423	SANDY CLAY & LIMEROCK	
20	423	23 446	SAND-FINE & SMALL & SANDY CLAY	
	446	460	BROWN CLAY FINE SAND & FEW LIMEROCK LEDGES	
60	460	13 473	SAND-FINE TO MED COURSE SMALL GRAVEL FEW CLAY STKS	
35	473	22 495	BROWN YELLOW & RED SANDSTONE FEW SOAPSTONE STKS	
35	495	15 510	GRAY SANDSTONE SHALE STKS	
	510	520	GRAY SOAPSTONE	

GARDEN CITY, KS  
 Phone 276-3278

6 SACKS QUIK-GEL, 1 SACK LIME, SET UP SOUTH PITS WEST  
 HENKLE DRILLING & SUPPLY CO., INC. SUBLETTE, KS  
 IRRIGATION HEADQUARTERS Phone 675-4311

TEST HOLES \* \* \* \* \* IRRIGATION & INDUSTRIAL WELLS \* \* \* \* \* STOCK WELLS