

The
Professionals

MINTER-WILSON DRILLING CO.

INCORPORATED

Irrigation
and Domestic
Water Systems
Complete Installation
and Repairing

Phone 276-6269 • P.O. Box A • GARDEN CITY, KANSAS 67846

DON LINBERG
HASKELL COUNTY
7-1-77

Location: SE 25-27-33

Static Water Level- 202

Pivot

0	1	Top soil
1	107	Brown clay
107	143	Med. to course gravel (Loose)
143	212	Fine to med. sand and gravel streaks of course gravel (Loose)
212	228	Brown clay
228	245	Fine to med. sand and gravel 10% clay (Loose)
245	252	Fine to med. sand and gravel 15% clay (Loose)
252	260	Fine to med. sand and gravel 10% clay (Loose)
260	368	Fine to med. sand and gravel (Loose)
368	395	Fine to med. sand and gravel 15% clay (Loose)
395	403	Brown sandy clay 30% Gravel
403	410	Fine to med/ .sand and gravel 10% clay (Loose)
410	416	Fine to med. sand and gravel (Loose)
416	436	Brown sandy clay
436	443	Fine to med. sand and gravel 10% clay (Loose)
443	455	Brown sandy clay
455	503	Brown sandy clay
503	515	Gray and yellow clay with brown rock (Hard)

250 Plain
90 Perf
30 Screen
75 Perf