

KSA 82a-1212

[illegible]

DRILLERS TEST LOG

CUSTOMERS NAME Bill Engler Sr. DATE 9-16-82
 STREET ADDRESS 810 Thompson TEST # 1 E. LOG Yes
 CITY & STATE Garden City, Kansas 67846 DRILLER Mai
 COUNTY Haskell QUARTER NW SECTION 22 TOWNSHIP 27 RANGE 34

LOCATION Approx 900' south and 300 ft. east of NW corner

Domestic Well location

%	FOOTAGE			DESCRIPTION OF STRATA	Static Water Level _____	
	From	Pay	To		Proposed Well Depth _____	
	0		2	Top Soil		
	2		43	Brown & brown sandy clay		
	43		58	Sand - fine to med & clay		
	58		90	Brown sandy clay - few small sand stks		
	90		99	Sand - fine to med coarse small to med gravel		
	99		108	Brown clay		
	108		135	Sand - fine to med coarse small to large gravel		
	135		195	Sand - fine to med coarse small to med & few large gravel, clay stks.		
75	195	16	211	Sand - fine to med coarse small to large gravel cemented, rough		
65	211	29	240	Sand - fine to med coarse small to med gravel few rough rock ledges		
55	240	28	268	Sand - fine to med coarse small to med gravel, sandy clay stks, cemented in places.		
	268		286	Brown sandy clay		
50	286	11	297	Sand - fine to med coarse small gravel, clay stks.		
	297		315	Brown & gray clay - sticky		
	315		322	Brown sandy clay		
50	322	05	327	Sand - fine to med coarse few small gravel		
20	327	08	335	Sand - fine to med coarse & sandy clay		
50	335	25	360	Sand - fine to med coarse small gravel and sandy clay stks		
	360		367	Sandy clay & small sand stks		
	367		390	Brown & brown sandy clay, very few sand stks		
55	390	10	400	Sand - fine to med coarse small gravel		
				5" PVC	Plain	Perf
				360 - 330		30'
				330 - 295	35'	
				295 - 285		10'
				285 - 265	20'	
				265 - 245		20'
				245 - 0 + 1	246'	
				TOTAL	301'	60'
				Reamed 9 7/8" Hole 360'		

GARDEN CITY, KS
 Phone 276-3278

TEST HOLES * * * * *

HENKLE DRILLING & SUPPLY CO., INC.
 IRRIGATION HEADQUARTERS

SUBLETTE, KS
 Phone 675-4311