

1 LOCATION OF WATER WELL:	Fraction	Section Number	Township Number	Range Number
COUNTY: 034 GRANT	SE of Lot 2 (NW NE)	03	T 27 S	R 35 W

Distance and direction from nearest town or city street address of well if located within city?  
 FROM RIUS; APPX 16 1/2 MILES NORTH & 1 MILE WEST

2 WATER WELL OWNER:	JOHN ENSZ	Board of Agriculture, Division of Water Resources
RR#, St. Address, Box # :	10606 N. ROAD V	Application Number: 20263
City, State, ZIP code :	ULYSSES, KS 67880-	

3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX:	4 DEPTH OF COMPLETED WELL 569 ELEVATION: 0																																								
<table border="1"> <tr> <td>/ \</td> <td></td> <td></td> <td></td> <td></td> </tr> <tr> <td>1</td> <td>---</td> <td>NW</td> <td>---</td> <td>NE</td> </tr> <tr> <td>M</td> <td></td> <td></td> <td></td> <td></td> </tr> <tr> <td>i</td> <td>W</td> <td>---</td> <td>---</td> <td>E</td> </tr> <tr> <td>l</td> <td></td> <td></td> <td></td> <td></td> </tr> <tr> <td>e</td> <td></td> <td></td> <td></td> <td></td> </tr> <tr> <td></td> <td>---</td> <td>SW</td> <td>---</td> <td>SE</td> </tr> <tr> <td>\ /</td> <td></td> <td></td> <td></td> <td></td> </tr> </table>	/ \					1	---	NW	---	NE	M					i	W	---	---	E	l					e						---	SW	---	SE	\ /					Depth(s) Groundwater Encountered 1. 0 ft. 2. 0 ft. 3. 0 ft. WELL'S STATIC WATER LEVEL 291 ft. below land surface measured on mo/day/yr 05/30/07 Pump test data: Well water was 351 ft. after 4 hours pumping 815 gpm Estimated Yield 0 gpm: Well water was 0 ft. after 0 hours pumping 0 gpm Bore Hole Diameter 24 in. to 569 ft., and in. to 0 ft. WELL WATER TO BE USED AS: 02 IRRIGATION Was a chemical/bacteriological sample submitted to department? No ; If yes, mo/day/yr sample was submitted Water well disinfected? Yes
/ \																																									
1	---	NW	---	NE																																					
M																																									
i	W	---	---	E																																					
l																																									
e																																									
	---	SW	---	SE																																					
\ /																																									

5 TYPE OF BLANK CASING USED: 01 STEEL	CASING JOINTS: WELDED
Blank casing diameter 16 in. to 569 ft., Dia in. to 0 ft., Dia in. to 0 ft.	
Casing height above land surface 12 in., weight 42 lbs/ft. Wall thickness or gauge No. .250	
TYPE OF SCREEN OR PERFORATION MATERIAL: 01 STEEL	
SCREEN OR PERFORATION OPENINGS ARE: 01 CONT. SLOT	

SCREEN PERFORATED INTERVALS:	From 325 ft. to 375 ft., From 0 ft. to 0 ft.
	From 424 ft. to 564 ft., From 0 ft. to 0 ft.
GRAVEL PACK INTERVALS:	From 20 ft. to 569 ft., From 0 ft. to 0 ft.
	From 0 ft. to 0 ft., From 0 ft. to 0 ft.

6 GROUT MATERIAL 03 BENTONITE	
Grout Intervals: From 0 ft. to 20 ft., From 0 ft. to 0 ft., From 0 ft. to 0 ft.	
What is the nearest source of possible contamination: 14 ABAND. WELL	
Direction from well? SOUTH	How many feet? 120

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	2	02 SILT 05 SAND			
2	21	07 FINE SAND			
21	53	04 SANDY CLAY 05 SAND			
53	106	05 SAND 11 GRAVEL			
106	110	05 SAND			
110	121	05 SAND 11 GRAVEL			
121	133	04 SANDY CLAY 05 SAND			
133	155	01 CLAY			
155	163	05 SAND 13 FINE GRAVEL 01 CLAY			
163	173	01 CLAY			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 05/24/07 and this record is true to the best of my knowledge and belief. Kansas	
Water Well Contractor's License No. 145	This Water Well Record was completed on (mo/day/yr) 06/22/07
under the business name of HENKLE DRILLING & SUPPLY	by (signature)

(Continued)

WATER WELL RECORD Form WWC-5 KSA 82a-1212

1 LOCATION OF WATER WELL:	Fraction	Section Number	Township Number	Range Number
COUNTY: 034 GRANT	1/4 1/4 SE 1/4	03	T 27 S	R 35 W

2 WATER WELL OWNER: JOHN ENSZ

RR#, St. Address, Box # : 10606 N. ROAD V

City, State, ZIP code : ULYSSES, KS 67880-

Board of Agriculture, Division of Water Resources

Application Number: 20263

FROM	TO	LITHOLOGIC LOG
173	177	05 SAND
177	183	05 SAND 13 FINE GRAVEL 14 MED GRAVEL
183	193	04 SANDY CLAY 05 SAND 01 CLAY
193	226	05 SAND
226	243	04 SANDY CLAY 05 SAND
243	283	05 SAND 13 FINE GRAVEL 01 CLAY
283	297	05 SAND 01 CLAY
297	310	05 SAND
310	317	04 SANDY CLAY
317	340	05 SAND
340	347	04 SANDY CLAY
347	353	05 SAND
353	420	04 SANDY CLAY 07 FINE SAND 08 MEDIUM SAND
420	444	07 FINE SAND
444	461	05 SAND 28 ROCK
461	467	04 SANDY CLAY
467	564	05 SAND 28 ROCK 01 CLAY
564	568	31 CALICHE
568	580	19 SHALE

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 05/24/07 and this record is true to the best of my knowledge and belief. Kansas

Water Well Contractor's License No. 145

This Water Well Record was completed on (mo/day/yr) 06/22/07

under the business name of HENKLE DRILLING & SUPPLY

by (signature)

*Brian R. Richmond*