

Kansas Department of Health and
Environment-Division of Environment
(Water well Contractors)
Topeka, Kansas 66620

MI-1023



MINTER-WILSON DRILLING CO.

INCORPORATED

Irrigation
and Domestic
Water Systems
Complete Installation
and Repairing

Phone 276-8269 • P.O. Box 493 • GARDEN CITY, KANSAS 67846

Dale Corley
Grant County
2-9-76

Location: W $\frac{1}{2}$ 11-27-36 Between SW $\frac{1}{2}$ & NW $\frac{1}{2}$

Static Water Level: 165

Test #1

0	6	Fine sandy clay
6	20	Brown clay
20	37	Brown clay & fine sand
37	50	Brown clay
50	63	Fine to med. sand
63	80	Brown sandy clay, streaks of fine sand (30%)
80	95	Fine to med. sand & fine gravel (10%) clay (loose)
95	133	Fine to med. sand & gravel (10%) clay
133	170	Fine to med. sand & gravel (loose)
170	183	Fine to med. sand & gravel, clay 10%
183	244	Fine to med. sand & gravel (loose)
244	255	Fine to med. sand & gravel (loose) small hard streaks of white rock
255	271	Fine to med. sand & gravel (loose)
271	290	Fine to med. sand & gravel, streak of coarse gravel (loose)
290	337	Med. to coarse gravel (loose)
337	354	Fine to med. sand & gravel, small streaks of coarse gravel, small hard streak of white rock
354	368	Fine to med. sand & gravel (loose) small hard streak of white rock
368	395	Brown clay & white rock (tight)
395	417	Brown clay (tight)
417	430	Brown, gray & yellow clay with brown rock (hard)