

WATER WELL RECORD Form WWC-5 KSA 82a-1212

1 LOCATION OF WATER WELL: Fraction Section Number Township Number Range Number
 COUNTY: GRANT NE 1/4 NE 1/4 SE 1/4 34 T 27 S R 37 W

Distance and direction from nearest town or city street address of well if located within city?
 FROM ULYSSES - 4 N. ON HIGHWAY 25 - 1 EAST AND 1/4 NORTH

2 WATER WELL OWNER: PUCKET, STEVE
 RR#, St. Address, Box #: 1360 E. ARIZONA AVE. Board of Agriculture, Division of Water Resources
 City, State, ZIP code: ULYSSES, KS 67880- Application Number:

3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX: 4 DEPTH OF COMPLETED WELL 436 ELEVATION: 0
 Depth(s) Groundwater Encountered 1. 0 ft. 2. 0 ft. 3. 0 ft.
 WELL'S STATIC WATER LEVEL 308 ft. below land surface measured on mo/day/yr 07/08/04
 Pump testdata: Well water was 0 ft. after 0 hours pumping 0 gpm
 Estimated Yield 40 gpm: Well water was 0 ft. after 0 hours pumping 0 gpm
 Bore Hole Diameter 9 in. to 436 ft., and in. to 0 ft.
 WELL WATER TO BE USED AS: DOMESTIC
 Was a chemical/bacteriological sample submitted to department? No ;
 If yes, mo/day/yr sample was submitted Water well disinfected? Yes

5 TYPE OF BLANK CASING USED: PVC CASING JOINTS: GLUED
 Blank casing diameter 5 in. to 436 ft., Dia in. to 0 ft., Dia in. to 0 ft.
 Casing height above land surface 12 in., weight 200 lbs/ft. Wall thickness or gauge No. 21
 TYPE OF SCREEN OR PERFORATION MATERIAL: PVC
 SCREEN OR PERFORATION OPENINGS ARE: SAW CUT

SCREEN PERFORATED INTERVALS: From 330 ft. to 390 ft., From 0 ft. to 0 ft.
 From 410 ft. to 430 ft., From 0 ft. to 0 ft.
 GRAVEL PACK INTERVALS: From 28 ft. to 436 ft., From 0 ft. to 0 ft.
 From 0 ft. to 0 ft., From 0 ft. to 0 ft.

6 GROUT MATERIAL BENTONITE
 Grout Intervals: From 6 ft. to 28 ft., From 0 ft. to 0 ft., From 0 ft. to 0 ft.
 What is the nearest source of possible contamination: SEPTIC TANK
 Direction from well? EAST How many feet? 140

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	20	01 TOPSOIL 32 TAN CLAY			
20	90	32 TAN CLAY			
90	100	32 TAN CLAY 02 FINE SAND			
100	140	32 TAN CLAY 11 BROWN CLAY 02 FINE SAND			
140	160	02 FINE SAND 32 TAN CLAY 19 LAYERS			
160	220	16 GRAY CLAY			
220	240	16 GRAY CLAY 10 FINE-MEDSAND			
240	280	37 FIN-COAR SAN 24 THINROCLAYER			
280	300	37 FIN-COAR SAN 11 BROWN CLAY 27 ROCK			
300	315	Last Circulation			

RECEIVED
 OCT 27 2004
 BUREAU OF WATER

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 07/09/04 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 179 This Water Well Record was completed on (mo/day/yr) 07/26/04 under the business name of JOB'S WELL SERVICE, INC. by (signature) Judith Curt

(Continued)

WATER WELL RECORD Form WWC-5 KSA 82a-1212

1 LOCATION OF WATER WELL:	Fraction	Section Number	Township Number	Range Number
COUNTY: GRANT	NE 1/4 NE 1/4 SE 1/4	34	T 27 S	R 37 W

2 WATER WELL OWNER:	PUCKET, STEVE	
RR#, St. Address, Box # :	1360 E. ARIZONA AVE.	Board of Agriculture, Division of Water Resources
City, State, ZIP code :	ULYSSES, KS 67880-	Application Number:

FROM	TO	LITHOLOGIC LOG
315	430	29 SANDSTONE 16 GRAY CLAY

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 07/09/04 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 179 This Water Well Record was completed on (mo/day/yr) 07/26/04 under the business name of JOB'S WELL SERVICE, INC. by (signature) *Judith Cuck*