

1 LOCATION OF WATER WELL: Fraction Section Number Township Number Range Number
 COUNTY: 094 STANTON NW 1/4 NW 1/4 SE 1/4 15 T 27 S R 39 W

Distance and direction from nearest town or city street address of well if located within city?
 APPROX. 9 MILES NORTH AND 3/4 MILE WEST OF BIG BOW

2 WATER WELL OWNER: RACHEL JANE BERT TRUST
 RR#, St. Address, Box #: PO BOX 9 Board of Agriculture, Division of Water Resources
 City, State, ZIP code: SEDGWICK, KS 67135-0009 Application Number: 11,003

3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX: 4 DEPTH OF COMPLETED WELL 662 ELEVATION: 0
 Depth(s) Groundwater Encountered 1. 0 ft. 2. 0 ft. 3. 0 ft.
 WELL'S STATIC WATER LEVEL 212 ft. below land surface measured on mo/day/yr 04/17/98
 Pump testdata: Well water was 341 ft. after 4 hours pumping 1095 gpm
 Estimated Yield 1095 gpm: Well water was 0 ft. after 0 hours pumping 0 gpm
 Bore Hole Diameter 24 in. to 662 ft., and in. to 0 ft.
 WELL WATER TO BE USED AS: 02 IRRIGATION
 Was a chemical/bacteriological sample submitted to department? No ;
 If yes, mo/day/yr sample was submitted Water well disinfected? Yes

5 TYPE OF BLANK CASING USED: 01 STEEL CASING JOINTS: WELDED
 Blank casing diameter 16 in. to 662 ft., Dia in. to 0 ft., Dia in. to 0 ft.
 Casing height above land surface 12 in., weight 42 lbs/ft. Wall thickness or gauge No. .250
 TYPE OF SCREEN OR PERFORATION MATERIAL: 01 STEEL
 SCREEN OR PERFORATION OPENINGS ARE: 01 CONT. SLOT

SCREEN PERFORATED INTERVALS: From 282 ft. to 302 ft., From 357 ft. to 377 ft.
 From 327 ft. to 357 ft., From 378 ft. to 408 ft.
 GRAVEL PACK INTERVALS: From 20 ft. to 360 ft., From 0 ft. to 0 ft.
 From 360 ft. to 662 ft., From 0 ft. to 0 ft.

6 GROUT MATERIAL 03 BENTONITE
 Grout Intervals: From 0 ft. to 20 ft., From 0 ft. to 0 ft., From 0 ft. to 0 ft.
 What is the nearest source of possible contamination: 14 ABAND. WELL
 Direction from well? NORTHEAST How many feet? 270

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	2	02 SILT			
2	30	01 CLAY			
30	50	05 SAND 11 GRAVEL			
50	83	01 CLAY			
83	95	05 SAND 11 GRAVEL			
95	104	01 CLAY			
104	112	05 SAND 11 GRAVEL			
112	165	01 CLAY			
165	186	05 SAND 28 ROCK			
186	197	01 CLAY			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 04/14/98 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 145 This Water Well Record was completed on (mo/day/yr) 04/28/98 under the business name of HENKLE DRILLING & SUPPLY by (signature)

1 LOCATION OF WATER WELL: | Fraction | Section Number | Township Number | Range Number
 COUNTY: 094 STANTON | NW 1/4 NW 1/4 SE 1/4 | 15 | T 27 S | R 29 W

2 WATER WELL OWNER: RACHEL JANE BERT TRUST
 RR#, St. Address, Box #: PO BOX 9 Board of Agriculture, Division of Water Resources

City, State, ZIP code : SEDGWICK, KS 67135-0009 Application Number: 11,003

SCREEN PERFORATED INTERVALS: From 487 ft. to 527 ft., From 0 ft. to 0 ft.
 From 547 ft. to 657 ft., From 0 ft. to 0 ft.

FROM	TO	LITHOLOGIC LOG
197	220	05 SAND 11 GRAVEL
220	282	04 SANDY CLAY 20 LIMESTONE 05 SAND
282	296	05 SAND 11 GRAVEL 01 CLAY
296	326	04 SANDY CLAY 07 FINE SAND 08 MEDIUM SAND
326	336	07 FINE SAND 08 MEDIUM SAND 09 COARSE SAND
336	357	05 SAND 11 GRAVEL
357	370	31 CALICHE 23 SANDSTONE
370	380	19 SHALE
380	407	19 SHALE 23 SANDSTONE
407	470	19 SHALE 20 LIMESTONE
470	490	19 SHALE 23 SANDSTONE
490	525	23 SANDSTONE 19 SHALE
525	545	19 SHALE
545	659	23 SANDSTONE
659	665	20 LIMESTONE 31 CALICHE 01 CLAY
665	670	19 SHALE

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 04/14/98 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 145 This Water Well Record was completed on (mo/day/yr) 04/28/98 under the business name of HENKLE DRILLING & SUPPLY by (signature) *Bruce J. Reichmuth*